PROJECT REFERENCE NO.	SHEET NO.
U-4737	3
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201440

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0043000000-N	226	Lump Sum		GRADING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	275	TON	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS
0366000000-E	310	392	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	1,214	LF	18" RC PIPE CULVERTS, CLASS III
0378000000-E	310	188	LF	24" RC PIPE CULVERTS, CLASS III
0762000000-E	310	364	LF	66" BIT COAT CS PIPE CULVERTS, TYPE B 0.138" THICK
0774000000-E	310	378	LF	78" BIT COAT CS PIPE CULVERTS, TYPE B 0.168" THICK
0995000000-E	340	203	LF	PIPE REMOVAL
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1489000000-E	610	3,800	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	3,220	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	2,370	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	458	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2000000000-N	806	28	EA	RIGHT OF WAY MARKERS
2022000000-E	815	224	CY	SUBDRAIN EXCAVATION
2033000000-E	815	168	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	1,000	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	30	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	2	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	12	LF	6" OUTLET PIPE (SUBDRAINS)

ItemNumber	Sec #	Quantity	Unit	Description
2220000000-E	838	40	CY	REINFORCED ENDWALLS
2286000000-N	840	20	EA	MASONRY DRAINAGE STRUCTURES
2364000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.16
2374000000-N	840	1	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)
2374000000-N	840	10	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)
2374000000-N	840	4	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
2396000000-N	840	1	EA	FRAME WITH COVER, STD 840.54
2440000000-N	840	2	EA	CONCRETE APRON FOR CATCH BASIN
2451000000-N	840	2	EA	CONCRETE APRON FOR DROP INLETS
2542000000-E	846	2,650	LF	1'-6" CONCRETE CURB & GUTTER
2549000000-E	846	4,950	LF	2'-6" CONCRETE CURB & GUTTER
2591000000-E	848	2,550	SY	4" CONCRETE SIDEWALK
2598000000-E	848	110	SY	CONCRETE WHEELCHAIR RAMPS
2655000000-E	852	135	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
3649000000-E	876	14	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	45	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	168	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	30	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	96	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	50	EA	DRUMS
4446100000-E	SP	100	LF	BARRICADES (TYPE III)
4686000000-E	1205	3,550	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4695000000-E	1205	350	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
4710000000-E	1205	75	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)

ItemNumber	Sec #	Quantity	Unit	Description
4721000000-E	1205	16	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)
4725000000-E	1205	19	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
4810000000-E	1205	4,750	LF	PAINT PAVEMENT MARKING LINES (4")
4820000000-E	1205	350	LF	PAINT PAVEMENT MARKING LINES (8")
4835000000-E	1205	75	LF	PAINT PAVEMENT MARKING LINES (24")
4840000000-N	1205	8	EA	PAINT PAVEMENT MARKING CHARAC-TER
4845000000-N	1205	13	EA	PAINT PAVEMENT MARKING SYMBOL
6000000000-E	1605	3,000	LF	TEMPORARY SILT FENCE
6009000000-E	1610	100	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	100	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2	ACR	TEMPORARY MULCHING
6018000000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	1	TON	FERTILIZER FOR TEMPORARY SEED-ING
6030000000-E	1630	50	CY	SILT EXCAVATION
6036000000-E	1631	500	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	250	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	4.25	ACR	SEEDING & MULCHING
6090000000-E	1661	200	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	1	TON	FERTILIZER FOR REPAIR SEEDING

5/14/99
09-FEB-2005 10:23
:ts\pitt\arlington blvd ext\arlington_ddc2.psh_3_blank.dgn
jaccanbullard AT