

PROJECT NO.	SHEET NO.	TOTAL NO.
37687	3	

SUMMARY OF QUANTITIES

PROJECT NO.	COUNTY	MAP NO.	ROUTE	DESCRIPTION	TYP	LENGTH	WIDTH	UNDERCUT EXCAVATION	GRADING	SURFACE COURSE, TYPE S9.5C TONS	LEVELING COURSE, TYPE S9.5C TONS	INTERMEDIATE COURSE, TYPE I19.0C TONS	BASE COURSE, TYPE B25.0C TONS	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	12" RCP, CLASS III LF	15" RCP, CLASS III LF	18" RCP, CLASS III LF	24" RCP, CLASS III LF	30" RCP, CLASS III LF	36" RCP, CLASS III LF	54" RCP, CLASS III LF	60" RCP, CLASS III LF		
37687	Union	1	SECRET SHORTCUT RD.	FROM MECKLENBURG CO. LINE TO ROCKY RIVER RD. (SR1514)	1 THRU 13	6.1	24	2,000.00	1.00	9,085	1,000	14,485	4,670	882	610	1,260	100.00	1,900.00	32.00	36.00	12.00	16.00	16.00	16.00		
TOTAL FOR PROJ NO. 37687						6.1	24	2,000.00	1.00	9,085	1,000	14,485	4,670	882	610	1,260	100.00	1,900.00	32.00	36.00	12.00	16.00	16.00	16.00		
GRAND TOTAL						6.1	24	2,000.00	1.00	9,085	1,000	14,485	4,670	882	610	1,260	100.00	1,900.00	32.00	36.00	12.00	16.00	16.00	16.00		
								54"X36" CMP ARCH PIPE	PIPE REMOVAL	INCIDENTAL STONE BASE	0" TO 1.5" MILLING	PIPE COLLARS	PIPE PLUGS	MASONRY DRAINAGE STR.	FRAME & GRATE, DETAIL 840.16	6" DRIVEWAYS	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOX	REMOVE & RESET GUARDRAIL	RELOCATE EXISTING WATER METER	TEMPORARY SILT FENCE	STONE FOR EROSION CONTROL, CLASS B	SEDIMENT CONTROL STONE	SILT EXCAVATION	MATTING (EROSION CONTROL)	SEED & MULCHING
								LF	LF	TONS	SY	EA	EA	EA	EA	SY	EA	EA	LF	EA	LF	TN	TN	CY	SY	AC
								8.00	600.00	1,200.00	7,500.00	24.00	1.00	1.00	1.00	640.00	22.00	20.00	700.00	10.00	6,000.00	1,500.00	800.00	1,000	2,000	10.00
								8.00	600.00	1,200.00	7,500.00	24.00	1.00	1.00	1.00	640.00	22.00	20.00	700.00	10.00	6,000.00	1,500.00	800.00	1,000	2,000	10.00
GRAND TOTAL						6.1	24	8.00	600.00	1,200.00	7,500.00	24.00	1.00	1.00	1.00	640.00	22.00	20.00	700.00	10.00	6,000.00	1,500.00	800.00	1,000	2,000	10.00