

PROJECT R-2552AA

COUNTY WAKE-JOHNSTON

COMPUTED BY: BCF 01/05
 CHECKED BY: SCL 01/05

SHEET 2 OF 6

STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	UNSUIT. EXCAV.	SUITABLE EARTH EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	UNDERCUT EMB.	EMB. + 20 %	BORROW	ROCK WASTE	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
-IYI- LT.																
10+40.000	20+80.000	15,808	0	0	1,762	14,046	2,790	0	2,790	0	3,348	0	0	10,698	1,762	12,460
SUBTOTAL:		15,808	0	0	1,762	14,046	2,790	0	2,790	0	3,348	0	0	10,698	1,762	12,460
-Y2-																
12+05.075 END BRIDGE	13+00.000	21	0	0	0	21	437	0	437	0	524	503	0	0	0	0
SUBTOTAL:		21	0	0	0	21	437	0	437	0	524	503	0	0	0	0
-IYI- LT. INCLUDES -FLYLWREV- STA. 23+00.080 TO STA. 26+66.154																
20+80.000	26+80.000	28,513	0	2,783	11,571	16,942	5,383	0	2,600	2,783	6,460	0	0	10,482	14,354	24,836
SUBTOTAL:		28,513	0	2,783	11,571	16,942	5,383	0	2,600	2,783	6,460	0	0	10,482	14,354	24,836
-IYI- LT.																
26+80.000	33+00.000	2,728	0	0	0	2,728	2,272	0	2,272	0	2,726	0	0	2	0	2
-IYI- LT. INCLUDES -RPD- STA. 15+47.035 TO STA. 17+57.082																
33+00.000	41+60.000	10,530	0	70	3,197	7,333	2,273	0	2,203	70	2,728	0	0	4,605	3,267	7,872
SUBTOTAL:		13,258	0	70	3,197	10,061	4,545	0	4,475	70	5,454	0	0	4,607	3,267	7,874
-IYI- RT. INCLUDES -FLYLREVV- STA. 31+76.908 TO STA. 35+02.248																
10+40.000	20+00.000	75,138	0	0	0	75,138	2,991	0	2,991	0	3,589	0	0	71,549	0	71,549
SUBTOTAL:		75,138	0	0	0	75,138	2,991	0	2,991	0	3,589	0	0	71,549	0	71,549
-Y2-																
10+60.000	10+96.275 BEGIN BRIDGE	205	0	0	0	205	0	0	0	0	0	0	0	205	0	205