

PROJECT R-2552AA

COUNTY WAKE-JOHNSTON

COMPUTED BY: BCF 01/05
 CHECKED BY: SCL 01/05

SHEET 1 OF 6

| STATION | STATION | TOTAL EXCAV. (UNCL.) | ROCK EXCAV. | UNDERCUT EXCAV. | UNSUIT. EXCAV. | SUITABLE EARTH EXCAV. | TOTAL EMB. | ROCK EMB. | EARTH EMB. | UNDERCUT EMB. | EMB. + 20 % | BORROW | ROCK WASTE | SUITABLE WASTE | UNSUIT. WASTE | TOTAL WASTE |
|---------------------------------------|-----------|----------------------|-------------|-----------------|----------------|-----------------------|------------|-----------|------------|---------------|-------------|--------|------------|----------------|---------------|-------------|
| TEMPORARY -IYI- MEDIAN | | | | | | | | | | | | | | | | |
| LEFT | | | | | | | | | | | | | | | | |
| 8+60.000 | 43+40.000 | 1,608 | 0 | 0 | 0 | 1,608 | 523 | 0 | 523 | 0 | 628 | 0 | 0 | 980 | 0 | 980 |
| RIGHT | | | | | | | | | | | | | | | | |
| 8+60.000 | 38+05.000 | 1,361 | 0 | 0 | 0 | 1,361 | 443 | 0 | 443 | 0 | 532 | 0 | 0 | 829 | 0 | 829 |
| CROSSOVERS | | | | | | | | | | | | | | | | |
| SEE DETAIL FOR STATION RANGES | | 161 | 0 | 0 | 0 | 161 | 247 | 0 | 247 | 0 | 296 | 135 | 0 | 0 | 0 | 0 |
| SUBTOTAL: | | 3,130 | 0 | 0 | 0 | 3,130 | 1,213 | 0 | 1,213 | 0 | 1,456 | 135 | 0 | 1,809 | 0 | 1,809 |
| TEMPORARY -IYI- MEDIAN REMOVAL | | | | | | | | | | | | | | | | |
| LEFT | | | | | | | | | | | | | | | | |
| 8+60.000 | 43+40.000 | 523 | 0 | 0 | 0 | 523 | 1,608 | 0 | 1,608 | 0 | 1,930 | 1,407 | 0 | 0 | 0 | 0 |
| RIGHT | | | | | | | | | | | | | | | | |
| 8+60.000 | 38+05.000 | 443 | 0 | 0 | 0 | 443 | 1,361 | 0 | 1,361 | 0 | 1,633 | 1,190 | 0 | 0 | 0 | 0 |
| CROSSOVERS | | | | | | | | | | | | | | | | |
| SEE DETAIL FOR STATION RANGES | | 247 | 0 | 0 | 0 | 247 | 161 | 0 | 161 | 0 | 193 | 0 | 0 | 54 | 0 | 54 |
| SUBTOTAL: | | 1,213 | 0 | 0 | 0 | 1,213 | 3,130 | 0 | 3,130 | 0 | 3,756 | 2,597 | 0 | 54 | 0 | 54 |