

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+99.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0241000000-E	SP	GENERIC GRADING ITEM ROCK-PLATED EMBANKMENT	480 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	24 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	92 LF		
0012	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (96", 0.109")	105 LF		
0013	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0014	0995000000-E	340	PIPE REMOVAL	105 LF		
0015	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0016	1121000000-E	520	AGGREGATE BASE COURSE	115 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1330000000-E	607	INCIDENTAL MILLING	100	SY	
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	205	TON	
0020	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	140	TON	
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	18	TON	
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30	TON	
0023	2000000000-N	806	RIGHT OF WAY MARKERS	12	EA	
0024	2022000000-E	815	SUBDRAIN EXCAVATION	67.2	CY	
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	50.4	CY	
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300	LF	
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9	EA	
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0030	2199000000-E	SP	SANDBAG HEADWALL	1,235	SF	
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4	EA	
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1	EA	
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3	EA	
0034	2516000000-E	SP	SELECT GRANULAR MATERIAL FOR TEMPORARY FABRIC WALL	135	CY	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2517000000-E	SP	FABRIC FOR TEMPORARY FABRIC WALL	950 SY		
0036	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
0037	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	105 LF		
0038	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0039	3030000000-E	862	STEEL BM GUARDRAIL	75 LF		
0040	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	2 EA		
0043	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1 EA		
0045	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0046	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	250 LF		
0047	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0048	3649000000-E	876	PLAIN RIP RAP, CLASS B	26 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,080 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0051	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	154 SF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0053	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		
0054	4430000000-N	1130	DRUMS	30 EA		
0055	4435000000-N	1135	CONES	15 EA		
0056	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0057	4450000000-N	1150	FLAGGER	2,400 HR		
0058	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0059	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	2 EA		
006C	4485000000-E	1170	PORTABLE CONCRETE BARRIER	300 LF		
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	38 EA		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,700 LF		
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	40 LF		
0064	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	58 EA		
0065	6000000000-E	1605	TEMPORARY SILT FENCE	580 LF		
0066	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0067	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	110 TON		
0068	6012000000-E	1610	SEDIMENT CONTROL STONE	235 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0070	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0071	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0072	6024000000-E	1622	TEMPORARY SLOPE DRAINS	40 LF		
0073	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0074	6029000000-E	SP	SAFETY FENCE	500 LF		
0075	6030000000-E	1630	SILT EXCAVATION	170 CY		
0076	6036000000-E	1631	MATTING FOR EROSION CONTROL	435 SY		
0077	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0078	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0079	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0080	6087000000-E	1660	MOWING	0.5 ACR		
0081	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0082	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0083	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0084	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0085	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0086	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0087	6123000000-E	1670	REFORESTATION	0.28 ACR		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0088	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+99.00-L-)	Lump Sum	L.S.	
0089	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+99.00-L-)	Lump Sum	L.S.	
009C	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	12 LF		
0091	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	32 LF		
0092	8113000000-N	SP	SID INSPECTION	1 EA		
0093	8114000000-N	SP	SPT TESTING	1 EA		
0094	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0095	8116000000-E	SP	CSL TUBES	216 LF		
0096	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+99.00-L-)	Lump Sum	L.S.	
0097	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	61.9 CY		
0098	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+99.00-L-)	Lump Sum	L.S.	
0099	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,475 LB		
010C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,478 LB		
0101	8364000000-E	450	HP12X53 STEEL PILES	140 LF		
0102	8503000000-E	460	CONCRETE BARRIER RAIL	214.21 LF		
0103	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	149 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	167 SY		
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0106	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	963.94 LF		

1137/Mar31/Q39252.93/D450853780000/E106

Total Amount Of Bid For Entire Project :

C201258 (B-3709)
COUNTY: Watauga County

2/16/99

Contract No: C201258
County: Watauga

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

1
2

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General