

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.5 -L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0008	0106000000-E	230	BORROW EXCAVATION	12,300 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	230 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	29 TON		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	140 LF		
0015	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	120 LF		
0016	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	8 LF		
0017	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0018	0995000000-E	340	PIPE REMOVAL	110 LF		
0019	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,550 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,220 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	880 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	182 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0025	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0026	2022000000-E	815	SUBDRAIN EXCAVATION	230 CY		
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0029	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0030	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0031	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0033	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.64 LF		
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	10 LF		
0037	3030000000-E	862	STEEL BM GUARDRAIL	362.5 LF		
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0041	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	2 EA		
0042	3649000000-E	876	PLAIN RIP RAP, CLASS B	25 TON		
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	200 SY		
0044	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0045	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	84 SF		
0046	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0047	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0048	4430000000-N	1130	DRUMS	60 EA		
0049	4435000000-N	1135	CONES	60 EA		
0050	4446100000-E	SP	BARRICADES (TYPE III)	40 LF		
0051	4450000000-N	1150	FLAGGER	320 HR		
0052	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0053	4485000000-E	1170	PORTABLE CONCRETE BARRIER	245 LF		
0054	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	222 LF		
0055	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	22 EA		
0056	4730000000-E	1205	EPOXY PAVEMENT MARKING LINES (4")	6,900 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,800	LF	
0058	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	400	LF	
0059	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	2	EA	
0060	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	19	EA	
0061	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	12	TON	
0062	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	12	TON	
0063	5444000000-E	1510	6" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)	238	LF	
0064	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	300	LB	
0065	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	2	EA	
0066	5888000000-E	SP	GENERIC UTILITY ITEM 8" HDPE WATER PIPE, SDR 9, 200 # WP BY DIRECTIONAL BORE	416	LF	
0067	6000000000-E	1605	TEMPORARY SILT FENCE	2,190	LF	
0068	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0069	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	380	TON	
0070	6012000000-E	1610	SEDIMENT CONTROL STONE	160	TON	
0071	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200	LB	
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75	TON	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6024000000-E	1622	TEMPORARY SLOPE DRAINS	240 LF		
0075	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0076	6029000000-E	SP	SAFETY FENCE	800 LF		
0077	6030000000-E	1630	SILT EXCAVATION	900 CY		
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	700 SY		
0079	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0080	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0081	6087000000-E	1660	MOWING	3 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25 TON		
0086	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0087	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0088	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

0089	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+05.50-L-)	Lump Sum	L.S.	
0090	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+05.50-L-)	Lump Sum	L.S.	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	196 LF		
0092	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	60 LF		
0093	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	37 LF		
0094	8113000000-N	SP	SID INSPECTION	4 EA		
0095	8114000000-N	SP	SPT TESTING	4 EA		
0096	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0097	8116000000-E	SP	CSL TUBES	1,064 LF		
0098	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,510 SF		
0099	8161000000-E	420	GROOVING BRIDGE FLOORS	6,067 SF		
0100	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	96.7 CY		
0101	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+05.50-L-)	Lump Sum	L.S.	
0102	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,818 LB		
0103	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,201 LB		
0104	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	728.333 LF		
0105	8364000000-E	450	HP12X53 STEEL PILES	480 LF		
0106	8503000000-E	460	CONCRETE BARRIER RAIL	295.833 LF		
0107	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	355 TON		
0108	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	395 SY		
0109	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0825/Apr28/Q108912.506/D487984080000/E109			Total Amount Of Bid For Entire Project :			

C200891 (B-3714)
COUNTY: Wilkes County

2/16/99

Contract No: C200891
County: Wilkes

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)