PROJ. REFERENCE NO.	SHEET NO.
112.1044027	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -EL4-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)		Station -EY-	Uncl. Exc. (cu. yd.)	Select Material Class VII (cu. yd.)
18+50.00	0.00	0.00		19+50.00	0.00	0.00
18+75.00	4.30	7.15		19+75.00	19.44	190.79
19+00.00	4.78	5.73		20+00.00	27.76	382.25
19+25.00	5.44	4.97		20+25.00	28.81	367.52
19+50.00	6.35	3.36		20+50.00	27.25	330.43
19+75.00	6.57	3.53		20+75.00	27.19	328.51
20+00.00	6.53	4.45		21+00.00	25.31	340.45
20+25.00	6.50	4.33		21+25.00	20.32	318.94
20+50.00	6.39	4.15		21+50.00	20.94	318.73
20+75.00	6.28	3.74		21+75.00	25.88	323.59
21+00.00	349.69	40.95		22+00.00	23.25	273.42
21+25.00	1171.39	39.20		22+25.00	25.93	242.41
21+50.00	1849.58	124.50		22+50.00	26.00	274.88
21+75.00	1821.33	366.07		22+75.00	22.95	275.94
22+00.00	1382.67	443.59		23+00.00	25.64	271.17
22+25.00	1035.68	454.69		23+25.00	16.61	363.15
22+50.00	521.52	927.51		23+50.00	6.35	454.36
22+75.00	156.32	1030.15		23+75.00	12.50	441.45
23+00.00	220.36	671.10		24+00.00	21.90	359.56
23+25.00	293.92	589.58		24+25.00	23.50	330.85
23+50.00	411.14	460.85		24+50.00	31.11	311.60
				24+75.00	39.85	300.14
				25+00.00	34.47	339.24
				25+25.00	20.64	427.41
				25+50.00	10.16	507.22
				25+75.00	7.48	520.94
				26+00.00	6.32	538.80
				26+25.00	16.15	521.47
				26+50.00	24.96	469.69
				26+75.00	28.32	394.81