

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0241000000-E	SP	GENERIC GRADING ITEM GALVANIZED CHAINLINK MESH	2,900 SY		
0006	0241000000-E	SP	GENERIC GRADING ITEM RING NET	7,250 SY		
0007	0255000000-E	SP	GENERIC GRADING ITEM RIP RAP MATERIALS, CLASS A	2,175 TON		
0008	0257000000-E	SP	GENERIC GRADING ITEM GROUTED ROCK DOWEL	360 LF		
0009	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VII)	16,350 TON		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	34 TON		
0011	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	320 LF		
0012	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0013	0995000000-E	340	PIPE REMOVAL	30 LF		
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	280 SY		
0015	1330000000-E	607	INCIDENTAL MILLING	30 SY		
0016	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	430 TON		
0017	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	50 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1539000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	100 TON		
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	20 TON		
0020	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	10 TON		
0021	1840000000-E	665	MILLED RUMBLE STRIPS	500 LF		
0022	1891000000-E	SP	GENERIC PAVING ITEM UNREINFORCED CONCRETE	110 SY		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0024	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0025	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0026	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2 EA		
0027	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (STD 854.02 T)	500 LF		
0028	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0029	3628000000-E	876	PLAIN RIP RAP, CLASS I	30 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	150 SY		
0031	3980000000-E	SP	GENERIC WALL ITEM GROUT FOR TIEBACK ANCHORS AT WALL AT SLIDE #4	50 CY		
0032	3984000000-E	SP	GENERIC WALL ITEM PERMANENT ANCHOR TIEBACK WALL AT SLIDE #4	4,850 SF		
0033	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	96 SF		
0034	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	104 SF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0036	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	1 EA		
0037	4430000000-N	1130	DRUMS	45 EA		
0038	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0039	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	1 EA		
0040	4485000000-E	1170	PORTABLE CONCRETE BARRIER	700 LF		
0041	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	1,430 LF		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,300 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0049	6030000000-E	1630	SILT EXCAVATION	60 CY		
0050	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,250 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	380 LF		
0052	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0053	6087000000-E	1660	MOWING	0.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0058	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0059	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0060	6123000000-E	1670	REFORESTATION	1 ACR		

1402/May19/Q46368.25/D203669600000/E60

Total Amount Of Bid For Entire Project :

C201464
COUNTY: Haywood County

2/16/99

Contract No: C201464
County: Haywood

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General