

7/22/99

REVISIONS

| | |
|-----------------------|-----------|
| PROJECT REFERENCE NO. | SHEET NO. |
| B-3887 | 3 |
| RW SHEET NO. | |

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200965

| ItemNumber | Sec # | Quantity | Unit | Description | ItemNumber | Sec # | Quantity | Unit | Description |
|--------------|-------|----------|------|--|--------------|-------|----------|------|---|
| 0000100000-N | 800 | Lump Sum | | MOBILIZATION | 4425000000-N | 1125 | 2 | EA | WARNING FLAG SETS |
| 0029000000-N | SP | Lump Sum | | REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+64.500) | 4446100000-E | SP | 72 | LF | BARRICADES (TYPE III) |
| 0043000000-N | 226 | Lump Sum | | GRADING | 4810000000-E | 1205 | 7,680 | LF | PAINT PAVEMENT MARKING LINES (4") |
| 0050000000-E | 226 | 1 | ACR | SUPPLEMENTARY CLEARING & GRUB- BING | 6000000000-E | 1605 | 525 | LF | TEMPORARY SILT FENCE |
| 0057000000-E | 226 | 200 | CY | UNDERCUT EXCAVATION | 6006000000-E | 1610 | 50 | TON | STONE FOR EROSION CONTROL, CLASS A |
| 0196000000-E | 270 | 200 | SY | FABRIC FOR SOIL STABILIZATION | 6009000000-E | 1610 | 105 | TON | STONE FOR EROSION CONTROL, CLASS B |
| 0318000000-E | 300 | 6 | TON | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 6012000000-E | 1610 | 40 | TON | SEDIMENT CONTROL STONE |
| 0660000000-E | 310 | 48 | LF | ***BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064") | 6015000000-E | 1615 | 1.5 | ACR | TEMPORARY MULCHING |
| 0680000000-E | 310 | 4 | EA | *** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064") | 6018000000-E | 1620 | 50 | LB | SEED FOR TEMPORARY SEEDING |
| 1489000000-E | 610 | 660 | TON | ASPHALT CONC BASE COURSE, TYPE B25.0B | 6021000000-E | 1620 | 0.25 | TON | FERTILIZER FOR TEMPORARY SEED- ING |
| 1525000000-E | SP | 280 | TON | ASPHALT CONC SURFACE COURSE, TYPE SP9.5A | 6024000000-E | 1622 | 50 | LF | TEMPORARY SLOPE DRAINS |
| 1560000000-E | 620 | 47 | TON | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 6027000000-N | 1622 | 2 | EA | INLET PROTECTION AT TEMPORARY SLOPE DRAINS |
| 2286000000-N | 840 | 2 | EA | MASONRY DRAINAGE STRUCTURES | 6029000000-E | SP | 300 | LF | SAFETY FENCE |
| 2367000000-N | 840 | 2 | EA | FRAME WITH TWO GRATES, STD 840.29 | 6030000000-E | 1630 | 215 | CY | SILT EXCAVATION |
| 2556000000-E | 846 | 285 | LF | SHOULDER BERM GUTTER | 6036000000-E | 1631 | 640 | SY | MATTING FOR EROSION CONTROL |
| 3030000000-E | 862 | 475 | LF | STEEL BM GUARDRAIL | 6042000000-E | 1632 | 40 | LF | 1/4" HARDWARE CLOTH |
| 3150000000-N | 862 | 5 | EA | ADDITIONAL GUARDRAIL POSTS | 6048000000-E | SP | 100 | SY | FLOATING TURBIDITY CURTAIN |
| 3215000000-N | 862 | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE III | 6084000000-E | 1660 | 1.5 | ACR | SEEDING & MULCHING |
| 3270000000-N | SP | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE 350 | 6087000000-E | 1660 | 1 | ACR | MOWING |
| 3649000000-E | 876 | 5 | TON | PLAIN RIP RAP, CLASS B | 6090000000-E | 1661 | 50 | LB | SEED FOR REPAIR SEEDING |
| 3656000000-E | 876 | 165 | SY | FILTER FABRIC FOR DRAINAGE | 6093000000-E | 1661 | 0.25 | TON | FERTILIZER FOR REPAIR SEEDING |
| 4412000000-E | SP | 256 | SF | WORK ZONE SIGNS (STATIONARY) | 6096000000-E | 1662 | 50 | LB | SEED FOR SUPPLEMENTAL SEEDING |
| 4412000000-E | SP | 94 | SF | WORK ZONE SIGNS (BARRICADE MOUNTED) | 6108000000-E | 1665 | 1.25 | TON | FERTILIZER TOPDRESSING |
| | | | | | 6114000000-N | SP | 1.5 | HR | SPECIALIZED HAND MOWING |
| | | | | | 6117000000-N | 1675 | 8 | EA | RESPONSE FOR EROSION CONTROL |