

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200958

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+75 -L-)
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (31+50 -L-)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	1,000	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0106000000-E	230	13,000	CY	BORROW EXCAVATION
0195000000-E	265	4,000	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	4,700	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	21	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0708000000-E	310	196	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1489000000-E	610	975	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1519000000-E	610	580	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	77	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2000000000-N	806	30	EA	RIGHT OF WAY MARKERS
2286000000-N	840	6	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	6	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	100	LF	SHOULDER BERM GUTTER
3030000000-E	862	1,150	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	8	EA	GUARDRAIL ANCHOR UNITS, TYPE III

ItemNumber	Sec #	Quantity	Unit	Description
3270000000-N	SP	8	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3656000000-E	876	480	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	6	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4025000000-E	901	8.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	16	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	2	EA	SIGN ERECTION, TYPE E
4155000000-N	907	12	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4412000000-E	SP	403	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4446100000-E	SP	128	LF	BARRICADES (TYPE III)
4685000000-E	1205	3,900	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	3,900	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4900000000-N	1252	180	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	4,120	LF	TEMPORARY SILT FENCE
6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	90	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	125	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	4	ACR	TEMPORARY MULCHING
6018000000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	190	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	8	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	4,030	LF	SAFETY FENCE

ItemNumber	Sec #	Quantity	Unit	Description
6030000000-E	1630	160	CY	SILT EXCAVATION
6036000000-E	1631	2,280	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
6084000000-E	1660	5	ACR	SEEDING & MULCHING
6087000000-E	1660	2.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	3.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	3.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

20-DCT-0004-10-19  
R0-P01-0006-16-10-19  
mevocal AT R01886-19