

**County: Halifax**  
**Project: B-3467**

**PROJECT SPECIAL PROVISIONS**

Utility

**UTILITIES BY OTHERS:**

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A) Halifax Electric Membership Corp. – Power (Distribution)**
- B) Sprint – Telephone**

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications.

Utilities Requiring Adjustment:

**A) Halifax Electric Membership Corp. – Power (Distribution)**

1. Station 15+50 to 28+00 Line -L- Left & Right (SR 1003-13 Bridges Road)  
The existing power pole line located right and left of Line -L- between stations 15+50 and 28+00 will remain in place. It will be de-energized at the appropriate times as necessary. The Contractor will notify the power company seven (7) calendar days prior to the date that the power company is to begin work. The power company will be given two (2) calendar days to complete work in this area. See Utilities By Others Plans for Details.
2. Station 28+00 to 35+46 Line -L- Left (SR 1003-13 Bridges Road)  
The existing power pole line located left of Line -L- between stations 28+00 and 35+46 will be dismantled and removed after a new power pole line has been installed between the same stations. It will be de-energized at the appropriate times as necessary. The Contractor will notify the power company seven (7) calendar days prior to the date that the power company is to begin work. The power company will be given two (2) calendar days to complete work in this area. See Utilities By Others Plans for Details.

**General Note:**

The Contractor shall allow intermittent re-energization at certain times when no hazardous work is being done near the conductors. This may occur several times over the course of the project. If an emergency situation should arise and re-energization is necessary, the Contractor shall immediately cease any hazardous construction and HEMC will re-energize to correct the situation, and de-energize as quickly as possible.

**B) Sprint – Telephone**

1. See Utilities By Others Plans for Details.