

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+75 -L-)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (31+50 -L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	13,000 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	4,000 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,700 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	21 TON		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	196 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	975 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	580 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	77 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	30 EA		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0021	3030000000-E	862	STEEL BM GUARDRAIL	1,150 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0025	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	480 SY		
0026	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6 EA		
0027	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	8.5 SF		
0028	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	16 LF		
0029	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0030	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	12 EA		
0031	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	403 SF		
0032	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0033	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0034	4446100000-E	SP	BARRICADES (TYPE III)	128 LF		
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,900 LF		
0036	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,900 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	180	EA	
0038	6000000000-E	1605	TEMPORARY SILT FENCE	4,120	LF	
0039	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150	TON	
0040	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	4	ACR	
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75	TON	
0045	6024000000-E	1622	TEMPORARY SLOPE DRAINS	190	LF	
0046	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8	EA	
0047	6029000000-E	SP	SAFETY FENCE	4,030	LF	
0048	6030000000-E	1630	SILT EXCAVATION	160	CY	
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,280	SY	
0050	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
0051	6070000000-N	SP	SPECIAL STILLING BASINS	4	EA	
0052	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0053	6087000000-E	1660	MOWING	2.5	ACR	
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100	LB	

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
0058	6114000000-N	SP	SPECIALIZED HAND MOWING	3.5 HR		
0059	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

**STRUCTURE ITEMS**

0060	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+75.00 -L-)	Lump Sum	L.S.	
0061	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (31+50.00 -L-)	Lump Sum	L.S.	
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+75.00 -L-)	Lump Sum	L.S.	
0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (31+50.00 -L-)	Lump Sum	L.S.	
0064	8112700000-N	SP	DYNAMIC LOAD TEST	2 EA		
0065	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+75.00 -L-)	Lump Sum	L.S.	
0066	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (31+50.00 -L-)	Lump Sum	L.S.	
0067	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	10,111 SF		
0068	8161000000-E	420	GROOVING BRIDGE FLOORS	10,735 SF		
0069	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	143.3 CY		
0070	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+75.00 -L-)	Lump Sum	L.S.	

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (31+50.00 -L-)	Lump Sum	L.S.	
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,530 LB		
0073	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	1,205.33 LF		
0074	8364000000-E	450	HP12X53 STEEL PILES	1,560 LF		
0075	8386000000-E	450	PP 18 X 0.50 STEEL PILES	1,490 LF		
0076	8503000000-E	460	CONCRETE BARRIER RAIL	613 LF		
0077	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	1,075 TON		
0078	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,196 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0080	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0081	8990000000-N	SP	CONTRACT TIME	1,000 DOL		

1350/Jun07/Q96301.63/D401649100000/E81

Total Amount Of Bid For Entire Project :

C200958 (B-3467)  
COUNTY: Halifax County

2/16/99

Contract No: C200958  
County: Halifax

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)