

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA-TION	50 TON		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS	16 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	80 LF		
001C	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
0011	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0012	0805000000-E	310	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	380 TON		
0015	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	290 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	36 TON		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0019	2556000000-E	846	SHOULDER BERM GUTTER	280 LF		
002C	3030000000-E	862	STEEL BM GUARDRAIL	650 LF		
0021	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0025	3649000000-E	876	PLAIN RIP RAP, CLASS B	7 TON		
0026	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	172 SY		
0027	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	418 SF		
0028	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0029	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	169 SF		
003C	4430000000-N	1130	DRUMS	20 EA		
0031	4435000000-N	1135	CONES	20 EA		
0032	4446100000-E	SP	BARRICADES (TYPE III)	132 LF		
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,400 LF		
0034	6000000000-E	1605	TEMPORARY SILT FENCE	850 LF		
0035	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	220 TON		
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	65 TON		
0038	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0039	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0041	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250 LF		
0042	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0043	6029000000-E	SP	SAFETY FENCE	350 LF		
0044	6030000000-E	1630	SILT EXCAVATION	715 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	900 SY		
0046	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0047	6045000000-E	SP	*** TEMPORARY PIPE (24")	150 LF		
0048	6069000000-E	1638	STILLING BASINS	330 CY		
0049	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
005C	6087000000-E	1660	MOWING	1 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6111000000-E	SP	IMPERVIOUS DIKE	45 LF		
0056	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0057	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

CULVERT ITEMS

0058	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+93.00 -L-)	Lump Sum	L.S.	
0059	8126000000-N	414	CULVERT EXCAVATION, STA ***** (15+93.00 -L-)	Lump Sum	L.S.	
0060	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	110 TON		
0061	8196000000-E	420	CLASS A CONCRETE (CULVERT)	157.9 CY		
0062	8245000000-E	425	REINFORCING STEEL (CULVERT)	29,647 LB		
0063	8590000000-E	876	PLAIN RIP RAP, CLASS ** (I)	62 TON		
0064	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	69 SY		

1529/Aug02/Q49173.65/D273743500000/E64

Total Amount Of Bid For Entire Project :

C201184 (B-3822)
COUNTY: Catawba County

2/16/99

Contract No: C201184
County: Catawba

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General