

FINAL PAVEMENT SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY	BREAKDOWN	TOTAL QUANTITY
FINAL PAVEMENT MARKINGS					
THERMOPLASTIC (4", 120 MILS)					
TC	10 FT. WHITE SKIP		2196	LF	
TD	2 FT. WHITE MINISKIP		307	LF	
TE	WHITE SOLID LANE LINE		3631	LF	
TI	YELLOW DOUBLE CENTER		1534	LF	
				TOTAL	7668 LF
THERMOPLASTIC (8", 90 MILS)					
TP	WHITE GORELINE		658	LF	
TQ	WHITE DIAGONAL		143	LF	
				TOTAL	801 LF
THERMOPLASTIC (24", 120 MILS)					
T2	WHITE STOPBAR		573	LF	
				TOTAL	573 LF
THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)					
UI	ALPHANUMERIC CHAR.		8	EA	
				TOTAL	8 EA
THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)					
UA	LEFT TURN ARROW		28	EA	
UB	RIGHT TURN ARROW		22	EA	
UC	STRAIGHT ARROW		29	EA	
UE	COMBO. STRAIGHT/RIGHT		5	EA	
UG	LEFT/RIGHT/STRAIGHT		1	EA	
				TOTAL	85 EA
COLD APPLIED PLASTIC (4")					
CC	10 FT. WHITE SKIP		218	LF	
				TOTAL	218 LF
MARKERS					
PERMANENT RAISED PAVEMENT MARKERS					
MB	CRYSTAL & RED		15	EA	
				TOTAL	15 EA
SNOWPLOWABLE RAISED PAVEMENT MARKERS					
MF	CRYSTAL & RED		293	EA	
				TOTAL	293 EA

25-JAN-2005 10:51
 \\ets-cctfso1\U3837\8\TCP\PM Plan\pml.dgn
 mmckoy AT TETC093445

APPROVED: <i>Joseph Ishak</i> DATE: <i>4/26/05</i>	FINAL PAVEMENT SCHEDULE	
	SCALE: NONE	
	DATE: MAY 2004	
	DESIGN BY: MM	
	REVIEWED BY: CBH	
	REVISIONS	