

PLAN OF SIDEWALK

NOTES

THE SIDEWALK IN A CONTINUOUS UNIT SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN THE UNIT HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.

THE JOINT IN THE DECK SHALL BE SAWED PRIOR TO THE CASTING OF THE SIDEWALK.

FOR SIDEWALK AND END POST QUANTITIES, SEE "SUPERSTRUCTURE - BILL OF MATERIAL" SHEET.

ALL REINFORCING STEEL IN SIDEWALK AND END POSTS SHALL BE EPOXY COATED.


FOR SIDEWALK COVER PLATE DETAILS, SEE "BRIDGE APPROACH SLAB DETAILS" SHEETS.

FOR CONCRETE INSERT DETAILS, SEE "3 BAR METAL RAIL", SHEET 3 OF 3.

THE #4 D1 DOWELS MAY BE PUSHED INTO GREEN CONCRETE AFTER THE SPAN HAS BEEN SCREEDED OFF, EXCEPT AS NOTED.

THESE DOWELS ARE TO BE PLACED AFTER SAWING OF THE JOINT. THE HOLES SHALL BE DRILLED AND THE DOWELS GROUTED IN PLACE.

GROOVED CONTRACTION JOINTS, \(\frac{1}{2}\)"IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE SIDEWALK IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINTS SHALL BE LOCATED AT A SPACING OF 8 FT. TO 10 FT. BETWEEN EXPANSION JOINTS. NO CONTRACTION JOINT WILL BE REQUIRED FOR SEGMENTS LESS THAN 10 FEET IN LENGTH.



END POST DETAILS



PROJECT NO. U-3837

FORSYTH COUNTY

STATION: 21+64.07 -L-

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

RALEIGH

SUPERSTRUCTURE

SIDEWALK DETAILS

----(RIGHT LANE)

REVISIONS						SHEET NO.
10.	BY:	DATE:	NO.	BY:	DATE:	S-61
1			3			TOTAL SHEETS
2			4			78

DRAWN BY : MIKE BRITT

CHECKED BY: William J. Parker

_ DATE : 12-5-03

_ DATE : ____05/26/04