



SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	PL. I.	% BY WEIGHT				% PASSING SIEVES			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-16	100 RT	27+50	0.00-1.50	A-6(5)	37	14	23.5	26.7	19.6	30.2	98	85	53		
SS-17	100 RT	27+50	4.30-5.80	A-7-6(7)	42	16	18.7	27.7	21.4	32.2	100	90	57		
SS-18	100 RT	27+50	14.30-15.80	A-2-4(0)	35	NP	42.8	38.0	15.2	4.0	92	67	22		
SS-25	140 LT	27+50	0.00-1.50	A-7-6(9)	44	22	22.7	24.5	14.6	38.2	96	84	54		
SS-26	140 LT	27+50	4.00-5.50	A-7-6(17)	58	29	20.1	20.1	17.6	42.2	98	85	62		
SS-27	140 LT	27+50	9.00-10.50	A-7-6(15)	56	26	18.7	23.7	17.4	40.2	100	91	61		

SS-26
SS-26
SS-27
27+50.00 -L-
140.00 LT.
RESIDUAL
RED SOFT TO MED. STIFF MOIST TO WET
MED. TO HIGH PLASTIC F. SANDY CLAY

SS-16
SS-17
SS-18
27+50.00 -L-
100.00 RT.
RESIDUAL
TAN-BRN MED. STIFF MOIST SILTY SANDY CLAY
ALLUVIUM
TAN-BRN MED. STIFF MOIST TO WET
SILTY F. SANDY CLAY
RESIDUAL
GRAY LOOSE MOIST TO WET
SILTY SAND W/ GRAVEL
RESIDUAL
GRAY MED. DENSE TO DENSE
WET SILTY F. & CSE. SAND

8/23/95
 SYSTEM TIME
 USER NAME