

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201289														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6018000000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (18+81.00)	3360000000-E	863	550	LF	REMOVE EXISTING GUARDRAIL	6021000000-E	1620	1	TON	FERTILIZER FOR TEMPORARY SEEDING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	3380000000-E	862	1,237.5	LF	TEMPORARY STEEL BM GUARDRAIL	6024000000-E	1622	220	LF	TEMPORARY SLOPE DRAINS
0057000000-E	226	500	CY	UNDERCUT EXCAVATION	3389100000-N	SP	6	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6027000000-N	1622	7	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0063000000-N	SP	Lump Sum		GRADING	3649000000-E	876	1	TON	PLAIN RIP RAP, CLASS B	6029000000-E	SP	250	LF	SAFETY FENCE
0106000000-E	230	28,600	CY	BORROW EXCAVATION	3656000000-E	876	155	SY	FILTER FABRIC FOR DRAINAGE	6030000000-E	1630	500	CY	SILT EXCAVATION
0195000000-E	265	5,000	CY	SELECT GRANULAR MATERIAL	3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6036000000-E	1631	1,510	SY	MATTING FOR EROSION CONTROL
0196000000-E	270	1,500	SY	FABRIC FOR SOIL STABILIZATION	4412000000-E	SP	126	SF	WORK ZONE SIGNS (STATIONARY)	6042000000-E	1632	100	LF	1/4" HARDWARE CLOTH
0318000000-E	300	26	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	4412100000-E	SP	144	SF	WORK ZONE SIGNS (PORTABLE)	6084000000-E	1660	6	ACR	SEEDING & MULCHING
0366000000-E	310	84	LF	15" RC PIPE CULVERTS, CLASS III	4412200000-E	SP	82	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6087000000-E	1660	2.5	ACR	MOWING
0708000000-E	310	56	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4430000000-N	1130	40	EA	DRUMS	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0714000000-E	310	100	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4435000000-N	1135	40	EA	CONES	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4446100000-E	SP	48	LF	BARRICADES (TYPE III)	6096000000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
1489000000-E	610	1,225	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4650000000-N	1251	15	EA	TEMPORARY RAISED PAVEMENT MARKERS	6108000000-E	1665	4.25	TON	FERTILIZER TOPDRESSING
1498000000-E	610	500	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4685000000-E	1205	2,290	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6114000000-N	SP	6	HR	SPECIALIZED HAND MOWING
1519000000-E	610	1,010	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4686000000-E	1205	4,580	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
1560000000-E	620	137	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4810000000-E	1205	17,388	LF	PAINT PAVEMENT MARKING LINES (4")	6123000000-E	1670	1.75	ACR	REFORESTATION
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES	4850000000-E	1205	1,900	LF	REMOVAL OF PAVEMENT MARKING LINES (4")					
2367000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29	4900000000-N	1252	14	EA	PERMANENT RAISED PAVEMENT MARKERS					
2556000000-E	846	592	LF	SHOULDER BERM GUTTER	6000000000-E	1605	2,750	LF	TEMPORARY SILT FENCE					
3030000000-E	862	1,300	LF	STEEL BM GUARDRAIL	6006000000-E	1610	100	TON	STONE FOR EROSION CONTROL, CLASS A					
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6009000000-E	1610	225	TON	STONE FOR EROSION CONTROL, CLASS B					
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6012000000-E	1610	100	TON	SEDIMENT CONTROL STONE					
					6015000000-E	1615	4	ACR	TEMPORARY MULCHING					

5/28/99

03-JUN-2005 11:0  
r:\roadway\estimate\final\bi1303\_rdy\_s03.dgn  
\$\$\$\$\$