

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+81.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	28,600 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	5,000 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	26 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84 LF		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0012	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	100 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,225 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	500 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,010 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	137 TON		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	592 LF		
0021	3030000000-E	862	STEEL BM GUARDRAIL	1,300 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0025	3360000000-E	863	REMOVE EXISTING GUARDRAIL	550 LF		
0026	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,237.5 LF		
0027	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0028	3649000000-E	876	PLAIN RIP RAP, CLASS B	1 TON		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	155 SY		
0030	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0031	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	126 SF		
0032	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	144 SF		
0033	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	82 SF		
0034	4430000000-N	1130	DRUMS	40 EA		
0035	4435000000-N	1135	CONES	40 EA		
0036	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0037	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	15 EA		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,290 LF		
0039	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,580 LF		
0040	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	17,388 LF		
0041	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,900 LF		
0042	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	14 EA		
0043	6000000000-E	1605	TEMPORARY SILT FENCE	2,750 LF		
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225 TON		
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	220 LF		
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0052	6029000000-E	SP	SAFETY FENCE	250 LF		
0053	6030000000-E	1630	SILT EXCAVATION	500 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,510 SY		
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0056	6084000000-E	1660	SEEDING & MULCHING	6 ACR		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6087000000-E	1660	MOWING	2.5 ACR		
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0060	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25 TON		
0062	6114000000-N	SP	SPECIALIZED HAND MOWING	6 HR		
0063	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0064	6123000000-E	1670	REFORESTATION	1.75 ACR		

STRUCTURE ITEMS

0065	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+81.00-L-)	Lump Sum	L.S.	
0066	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,790 CY		
0067	8161000000-E	420	GROOVING BRIDGE FLOORS	8,670 SF		
0068	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	66.6 CY		
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+81.00-L-)	Lump Sum	L.S.	
0070	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,618 LB		
0071	8364000000-E	450	HP12X53 STEEL PILES	1,700 LF		
0072	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (18+81.00-L-)	Lump Sum	L.S.	
0073	8503000000-E	460	CONCRETE BARRIER RAIL	359.25 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	580 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	640 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0078	8753000000-E	SP	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	2,694.38 LF		
0079	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	7,515 SF		

1621/Aug10/Q111010.48/D365371600000/E79

Total Amount Of Bid For Entire Project :

C201289 (B-1303)
COUNTY: Northampton County

2/16/99

Contract No: C201289
County: Northampton

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General