

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201294

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
001000000-E	200	Lump Sum		CLEARING & GRUBBING .. ACRE(S)
008000000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
002200000-E	225	550	CY	UNCLASSIFIED EXCAVATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** STA. 13+29.00 -L-
003600000-E	225	100	CY	UNDERCUT EXCAVATION
008000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZATION
013400000-E	240	42	CY	DRAINAGE DITCH EXCAVATION
015600000-E	250	250	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	25	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
034400000-E	310	60	LF	18" SIDE DRAIN PIPE
036600000-E	310	144	LF	15" RC PIPE CULVERTS, CLASS III
037200000-E	310	24	LF	18" RC PIPE CULVERTS, CLASS III
112100000-E	520	165	TON	AGGREGATE BASE COURSE
122000000-E	545	25	TON	INCIDENTAL STONE BASE
148900000-E	610	30	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	385	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	27	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	10	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
202200000-E	815	224	CY	SUBDRAIN EXCAVATION
203300000-E	815	168	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	1,000	LF	6" PERFORATED SUBDRAIN PIPE

ItemNumber	Sec #	Quantity	Unit	Description
205500000-E	815	30	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	2	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
207700000-E	815	12	LF	6" OUTLET PIPE (SUBDRAINS)
228600000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES
235500000-N	840	3	EA	FRAME WITH GRATE, STD 840.29
255600000-E	846	320	LF	SHOULDER BERM GUTTER
303000000-E	862	487.5	LF	STEEL BM GUARDRAIL
304500000-E	862	62.5	LF	STEEL BM GUARDRAIL, SHOP CURVED
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
363500000-E	876	7	TON	PLAIN RIP RAP, CLASS II
364900000-E	876	9	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	215	SY	FILTER FABRIC FOR DRAINAGE
402500000-E	901	6.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
407200000-E	903	13	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
410200000-N	904	1	EA	SIGN ERECTION, TYPE E
415500000-N	907	6	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
441200000-E	SP	444	SF	WORK ZONE SIGNS (STATIONARY)
441210000-E	SP	144	SF	WORK ZONE SIGNS (PORTABLE)
441220000-E	SP	45	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	6	EA	WARNING FLAG SETS
443500000-N	1135	50	EA	CONES
444610000-E	SP	68	LF	BARRICADES (TYPE III)

ItemNumber	Sec #	Quantity	Unit	Description
445500000-N	1150	12	MD	FLAGGER
446000000-N	1155	3	EA	WARNING LIGHTS (TYPE B)
481000000-E	1205	11,124	LF	PAINT PAVEMENT MARKING LINES (4")
483500000-E	1205	108	LF	PAINT PAVEMENT MARKING LINES (24")
600000000-E	1605	475	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	300	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	110	TON	SEDIMENT CONTROL STONE
601500000-E	1615	2.5	ACR	TEMPORARY MULCHING
601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
602900000-E	SP	220	LF	SAFETY FENCE
603000000-E	1630	1,000	CY	SILT EXCAVATION
603600000-E	1631	550	SY	MATTING FOR EROSION CONTROL
603800000-E	SP	655	SY	PERMANENT SOIL REINFORCEMENT MAT
604200000-E	1632	60	LF	1/4" HARDWARE CLOTH
608400000-E	1660	3.5	ACR	SEEDING & MULCHING
608700000-E	1660	1.5	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	2.5	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/05 15:11 15-JUN-2005 15:11 \\b-4266_Sum_Of_Quantities.dgn