

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	550 CY		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** STA. 13+29.00 -L-	Lump Sum	L.S.	
0006	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	42 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	250 SY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	25 TON		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	60 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	144 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	24 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	165 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	30 TON		
0019	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	385 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	27 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0029	2355000000-N	840	FRAME WITH GRATE, STD 840.29	3 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	320 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	487.5 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0037	3635000000-E	876	PLAIN RIP RAP, CLASS II	7 TON		
0038	3649000000-E	876	PLAIN RIP RAP, CLASS B	9 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	215 SY		
004C	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6.25 SF		
0041	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	13 LF		
0042	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0044	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	444 SF		
0045	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	144 SF		
0046	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	45 SF		
0047	4425000000-N	1125	WARNING FLAG SETS	6 EA		
0048	4435000000-N	1135	CONES	50 EA		
0049	4446100000-E	SP	BARRICADES (TYPE III)	68 LF		
005C	4455000000-N	1150	FLAGGER	12 MD		
0051	4460000000-N	1155	WARNING LIGHTS (TYPE B)	3 EA		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,124 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	108 LF		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	475 LF		
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	300 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0061	6029000000-E	SP	SAFETY FENCE	220 LF		
0062	6030000000-E	1630	SILT EXCAVATION	1,000 CY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	550 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	655 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0066	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0067	6087000000-E	1660	MOWING	1.5 ACR		
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0073	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+29.00-L-)	Lump Sum	L.S.	
0075	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	695 CY		
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	35.1 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+29.00-L-)	Lump Sum	L.S.	
0078	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,543 LB		
0079	8364000000-E	450	HP12X53 STEEL PILES	550 LF		
0080	8503000000-E	460	CONCRETE BARRIER RAIL	195.33 LF		
0081	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	254 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	282 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8753200000-E	SP	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,074.33 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	8990000000-N	SP	CONTRACT TIME	500 DOL		

0832/Aug10/Q30749.26/D343965700000/E85

Total Amount Of Bid For Entire Project :

C201294 (B-4266)
COUNTY: Rutherford County

2/16/99

Contract No: C201294
County: Rutherford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General