

SUMMARY OF QUANTITIES

Work Order No.	County / Municipality	Map No.	Route No./ Route Name	Description (To/From)	Typical No.	Length	Width	Incidental Stone Base	Mill Asph Pvmnt 1 1/2" Depth	Mill Asph Pvmnt 0" to 1 1/2" Depth	ACSC Type S9.5B	ACSC Leveling Course Type S9.5B	ACSC Type S9.5C	ACIC Type I19.0C	PG 64-22 Plant Mix	PG 70-22 Plant Mix	Patching Existing Pavement	Adjust Drop Inlet	Adjust Manholes	Adjust Meter / Valve Box
						MI	FT	TONS	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	EA	EA
9CR.10291.4	Davidson	1	NC 47	Pvmt Jt at SR 3160 (Legget & Platt Rd) to SR 1396 (Linwood-Southmont Rd)	2	0.438	24	13		500			705			43	10			
		1	NC 47 Junior Order Home Rd	SR 1396 (Linwood-Southmont Rd) to Pvmt Jt before NC 8	2	3.215	24	129	350	267			4,204	300	14	252	80		1	6
Sub-Total For Map No. 1						3.653		142	350	767	0	0	4,909	300	14	295	90	0	1	6
		2	NC 47	Pvmt Jt after SR 2248 (Allred Rd) to Pvmt Jt at SR 2310 (Shiptontown Rd)	2	2.600	22	104	112	384			3,118			187	65			4
		3	NC 47	SR 2347 (Yates Rd) to Denton NCL	2	2.092	24	84	280	400			2,736			164	60			
TOTAL FOR WORK ORDER NO. 9CR.10291.4						8.345		330	742	1,551	0	0	10,763	300	14	646	215	0	1	10
9CR.20291.4	Davidson	4	SR 1319 New Jersey Church Rd	Pvmt Jt at NC 47 to Pvmt Jt at SR 1272 (Jersey Church Rd)	1	2.048	24	82			2,678				161		30			1
		5	SR 1105 Riverwood Rd	Pvmt Jt at SR 1396 (Linwood-Southmont Rd) to SR 1106 (Beckner Rd)	1, 7	0.755	20	23			824	220			63		15			
		6	SR 2416 Old NC 109	SR 2205 (Old US 64) to EOP of NC 109	1	2.297	20	92		333	2,506				150		40			4
		7	SR 2116 Free Pilgrim Church Rd	SR 2115 (Cunningham Rd / Brick Yard Rd) to EOP of SR 2104 (Cunningham Rd)	1	1.324	19	53			1,373				83		45			2
		8	SR 2093 Ben Lee Rd	Pvmt Jt at NC 109 to SR 2094 (Lee Rd)	1	0.902	19	36			935				56		20			1
		9	SR 1772 Hasty School Rd	NC 109 to Thomasville NCL	2	1.080	24	43					1,412			85	40			
		10	SR 2205 Raleigh Rd	Lexington CL to Pvmt Jt before Bridge #431 (Abbott's Creek)	1	0.385	32	15			736				44		10			
TOTAL FOR WORK ORDER NO. 9CR.20291.4						8.791		344	0	333	9,052	220	1,412	0	557	85	200	0	0	8
9CR.302904.4	Denton	11	NC 47 Jones St	Denton NCL to 3rd Street (NS)	2, 6	0.170	24	3		200			222			14	10		2	2
		11	NC 47 Jones St	3rd Street (NS) to SR 2351 (W Salisbury St.)	4	0.287	30		5,051	167			469			28	25			
TOTAL FOR WORK ORDER NO. 9CR.302904.4						0.457		3	5,051	367	0	0	691	0	0	42	35	0	2	2
9CR.302911.4	Lexington	12	SR 2205 Raleigh Rd	Pvmt Jt at NC 8 (Talbert Avenue) to Lexington CL	1, 5	0.500	32	5		390	871				52		12		3	5
		13	SR 2000 Radio Rd	Pvmt Jt at US 64 to Lexington CL	1, 7	0.305	20	12			333	80			25		20			
TOTAL FOR WORK ORDER NO. 9CR.302911.4						0.805		17	0	390	1,204	80	0	0	77	0	32	0	3	5
9CR.302916.4	Thomasville	14	SR 1772 Hasty School Rd	US 29/70 to EOP of NC 68 (National Highway)	1	0.582	26	17			847				51		28		1	16
		15	SR 1772 Hasty School Rd	Thomasville NCL to beg 3 Lane at Shopping Center	2	1.056	24	42					1,381			83	50	1	3	6
		15	SR 1772 Hasty School Rd	3 Lane Section to EOP of NC 68 (National Highway)	6	0.252	33	5					519			31	20		3	1
Sub-Total For Map No. 15						1.308		47	0	0	0	0	1,900	0	0	114	70	1	6	7
		16	SR 2183 Fisher Ferry Rd	Pvmt Jt North of Trexler Ave (NS) to End of C&G Section	3	0.732	48			1,700	1,910				115		30			2
		16	SR 2183 Fisher Ferry Rd	End of C&G Section to Pvmt Jt at SR 2184 (Cedar Lodge Rd)	1	0.860	24	34		98	1,220				73		20			
Sub-Total For Map No. 16						0.860		34	0	1,798	3,130	0	0	0	188	0	50	0	0	2
TOTAL FOR WORK ORDER NO. 9CR.302916.4						3.482		98	0	1,798	3,977	0	1,900	0	239	114	148	1	7	25
GRAND TOTAL						21.880		792	5,793	4,439	14,233	300	14,766	300	887	887	630	1	13	50