

PROJECT NO.	SHEET NO.	TOTAL NO.
14CR.10441.2	3	4

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	5" MILLING SY	BASE COURSE, B25.0B (Widening) TONS	INTERMEDIATE COURSE, I19.0B TONS	INTERMEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	SF9.5A LEVELING TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 TONS	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22 TON
14CR.10441.2	Haywood	1	NC209	FROM WOOBIN ROAD TO PVMT CHNG 0.13 MIL SOUTH OF SR1355	1	2.68	32	5.36	13,911			2,522		4,480			387	
		2	NC209	FROM SR1334 TO PVMG CHNG 2.99 MI. SOUTH	2	2.99	20	5.98	9,797		1,696	1,776		3,124		2,083	479	
		3	NC209	FROM I-40 TO WOOBIN ROAD	3	0.2	40	0.29		4,693			803		526		38	32
TOTAL FOR PROJ NO. 14CR.10441.2						5.87		11.63	23,708	4,693	1,696	4,298	803	7,604	526	2,083	904	32
GRAND TOTAL						5.87		11.63	23,708	4,693	1,696	4,298	803	7,604	526	2,083	904	32