

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201197																			
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	205500000-E	815	9	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	443000000-N	1130	20	EA	DRUMS	608700000-E	1660	0.5	ACR	MOWING
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	443500000-N	1135	20	EA	CONES	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+96.30)	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	444610000-E	SP	64	LF	BARRICADES (TYPE III)	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
004300000-N	226	Lump Sum		GRADING	215400000-N	820	2	EA	METAL FUNNELS	445500000-N	1150	200	MD	FLAGGER	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	216500000-E	820	36	LF	12" FUNNEL DRAIN PIPE	481000000-E	1205	14,360	LF	PAINT PAVEMENT MARKING LINES (4")	610800000-E	1665	0.5	TON	FERTILIZER TOPDRESSING
005700000-E	226	200	CY	UNDERCUT EXCAVATION	217600000-E	820	2	EA	12" FUNNEL DRAIN PIPE ELBOWS	483000000-E	1205	342	LF	PAINT PAVEMENT MARKING LINES (16")	611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
008000000-E	SP	200	TON	CLASS IV SUBGRADE STABILIZATION	248600000-E	SP	770	SF	GENERIC DRAINAGE ITEM TEMPORARY SANDBAG HEADWALL	483500000-E	1205	300	LF	PAINT PAVEMENT MARKING LINES (24")	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
013400000-E	240	330	CY	DRAINAGE DITCH EXCAVATION	303000000-E	862	12.5	LF	STEEL BM GUARDRAIL	484000000-N	1205	16	EA	PAINT PAVEMENT MARKING CHARACTER	612300000-E	1670	0.23	ACR	REFORESTATION
019500000-E	265	700	CY	SELECT GRANULAR MATERIAL	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	485000000-E	1205	1,564	LF	REMOVAL OF PAVEMENT MARKING LINES (4")					
019600000-E	270	700	SY	FABRIC FOR SOIL STABILIZATION	318000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	486500000-E	1205	85	LF	REMOVAL OF PAVEMENT MARKING LINES (12")					
031800000-E	300	40	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	319500000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	487000000-E	1205	28	LF	REMOVAL OF PAVEMENT MARKING LINES (24")					
038400000-E	310	96	LF	30" RC PIPE CULVERTS, CLASS III	321500000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE III	487500000-N	1205	4	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS					
057600000-E	310	132	LF	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	327000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	600000000-E	1605	365	LF	TEMPORARY SILT FENCE					
058800000-E	310	76	LF	18" CS PIPE CULVERTS, 0.064" THICK	338000000-E	862	75	LF	TEMPORARY STEEL BM GUARDRAIL	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
059400000-E	310	24	LF	24" CS PIPE CULVERTS, 0.064" THICK	338200000-E	862	12.5	LF	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	600900000-E	1610	145	TON	STONE FOR EROSION CONTROL, CLASS B					
099500000-E	340	240	LF	PIPE REMOVAL	338700000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TYPE AT-1)	601200000-E	1610	415	TON	SEDIMENT CONTROL STONE					
112100000-E	520	450	TON	AGGREGATE BASE COURSE	338910000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	601500000-E	1615	0.5	ACR	TEMPORARY MULCHING					
133000000-E	607	50	SY	INCIDENTAL MILLING	362800000-E	876	75	TON	PLAIN RIP RAP, CLASS I	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING					
148900000-E	610	65	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	363500000-E	876	90	TON	PLAIN RIP RAP, CLASS II	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING					
152500000-E	SP	250	TON	ASPHALT CONC SURFACE COURSE, TYPE SP9.5A	364900000-E	876	55	TON	PLAIN RIP RAP, CLASS B	602900000-E	SP	140	LF	SAFETY FENCE					
156000000-E	620	20	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	365600000-E	876	1,195	SY	FILTER FABRIC FOR DRAINAGE	603000000-E	1630	655	CY	SILT EXCAVATION					
202200000-E	815	70	CY	SUBDRAIN EXCAVATION	441200000-E	SP	142	SF	WORK ZONE SIGNS (STATIONARY)	603600000-E	1631	525	SY	MATting FOR EROSION CONTROL					
203300000-E	815	55	CY	SUBDRAIN FINE AGGREGATE	441210000-E	SP	128	SF	WORK ZONE SIGNS (PORTABLE)	604200000-E	1632	40	LF	1/4" HARDWARE CLOTH					
204400000-E	815	300	LF	6" PERFORATED SUBDRAIN PIPE	441220000-E	SP	82	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	607000000-N	SP	16	EA	SPECIAL STILLING BASINS					
										608400000-E	1660	0.5	ACR	SEEDING & MULCHING					