

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+96.30)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	330 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	700 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	96 LF		
0013	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	132 LF		
0014	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	76 LF		
0015	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0016	0995000000-E	340	PIPE REMOVAL	240 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	450 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1330000000-E	607	INCIDENTAL MILLING	50	SY	
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	65	TON	
002C	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	250	TON	
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	20	TON	
0022	2022000000-E	815	SUBDRAIN EXCAVATION	70	CY	
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	55	CY	
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300	LF	
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9	EA	
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	2154000000-N	820	METAL FUNNELS	2	EA	
002E	2165000000-E	820	12" FUNNEL DRAIN PIPE	36	LF	
003C	2176000000-E	820	12" FUNNEL DRAIN PIPE ELBOWS	2	EA	
0031	2486000000-E	SP	GENERIC DRAINAGE ITEM TEMPORARY SANDBAG HEADWALL	770	SF	
0032	3030000000-E	862	STEEL BM GUARDRAIL	12.5	LF	
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	2	EA	
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2	EA	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	75 LF		
003E	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	12.5 LF		
004C	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TYPE AT-1)	1 EA		
0041	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	3 EA		
0042	3628000000-E	876	PLAIN RIP RAP, CLASS I	75 TON		
0043	3635000000-E	876	PLAIN RIP RAP, CLASS II	90 TON		
0044	3649000000-E	876	PLAIN RIP RAP, CLASS B	55 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,195 SY		
0046	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	142 SF		
0047	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	128 SF		
004E	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	82 SF		
0049	4430000000-N	1130	DRUMS	20 EA		
005C	4435000000-N	1135	CONES	20 EA		
0051	4446100000-E	SP	BARRICADES (TYPE III)	64 LF		
0052	4455000000-N	1150	FLAGGER	200 MD		
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,360 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	342 LF		
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	300 LF		
005E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	16 EA		
0057	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,564 LF		
005E	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	85 LF		
005E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	28 LF		
006C	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	4 EA		
0061	6000000000-E	1605	TEMPORARY SILT FENCE	365 LF		
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	145 TON		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	415 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
006E	6029000000-E	SP	SAFETY FENCE	140 LF		
006E	6030000000-E	1630	SILT EXCAVATION	655 CY		
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	525 SY		
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6070000000-N	SP	SPECIAL STILLING BASINS	16	EA	
0073	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0074	6087000000-E	1660	MOWING	0.5	ACR	
0075	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0076	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0078	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	
0079	6114000000-N	SP	SPECIALIZED HAND MOWING	1	HR	
008C	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
0081	6123000000-E	1670	REFORESTATION	0.23	ACR	

STRUCTURE ITEMS

0082	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+96.30-L-)	Lump Sum	L.S.	
0083	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	107	LF	
0084	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	44	LF	
008E	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	36.8	LF	
0086	8113000000-N	SP	SID INSPECTION	2	EA	
0087	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2	EA	
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	35.3	CY	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+96.30-L-)	Lump Sum	L.S.	
0090	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,434 LB		
0091	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,845 LB		
0092	8433000000-E	452	***" STEEL SHEET PILES (12")	1,431 SF		
0093	8475000000-E	460	TWO BAR METAL RAIL	68.46 LF		
0094	8517000000-E	460	1'-***"X *****" CONCRETE PARA- PET (1'-2" X 2'-8 3/8")	84.8 LF		
0095	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0096	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	381.61 LF		

0854/Dec06/Q44728.7/D400928340000/E96

Total Amount Of Bid For Entire Project :