

PROJECT NO.	SHEET NO.	TOTAL NO.
14CR.10501.2, 14CR.305005.2 14CR.305020.2, ETC.	3	7

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	1½" MILLING SY	4 1/2" MILLING SY	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SF9.5A LEVELING TON	PG 64-22 PLANT MIX TONS	DROP INLET EA	MANHOLES EA	METER OR VALVE BOX EA
14CR.10501.2	Jackson	1	US64	FROM ECL CASHIERS TO TRANSYLVANIA COUNTY LINE	3	6.27	22	9.83	18,030			1,035	3,268	7,206	4,804	942			
		2	US441	FROM US441 BUSINESS TO SR1391	4	0.53	60			20,264	10,490		1,901	1,661		190			
TOTAL FOR PROJ NO. 14CR.10501.2						6.8		9.83	18,030	20,264	10,490	1,035	5,169	8,867	4,804	1,132			
14CR.305005.2	Jackson	3	US64	FROM NC107 TO ECL CASHIERS	3	0.56	22	0.17	1,760			269	319	644	429	94			
TOTAL FOR PROJ NO. 14CR.305005.2						0.56		0.17	1,760			269	319	644	429	94			
14CR.305020.2	Jackson	4	US23 BUSINESS WEST	FROM US23 BUSINESS EAST TO US23 BUSINESS EAST	5	0.34	28		563	5,585			102	497		35	1	12	2
		5	SR1432	FROM US23 BUSINESS TO RXR CROSSING AT SR1429	1	0.66	23		1,666				308	808	337	85			
TOTAL FOR PROJ NO. 14CR.305020.2						1			2,229	5,585			410	1,305	337	120	1	12	2
40476	Jackson	6	NC107	FROM PVMT CHNG 263' NORTH OF US64 TO SR1142	2	1.26	22	2.52	4,347				781	1,434	956	185			
		7	NC107	FROM 440' NORTH OF SR1145 TO PVMT CHNG 0.38 MI. NORTH OF SR1145	2	0.3	21	0.60	751				135	326	217	40			
TOTAL FOR PROJ NO. 40476						1.56		3.12	5,098				916	1,760	1,173	225			
GRAND TOTAL						9.92		13.12	27,117	25,849	10,490	1,304	6,814	12,576	6,743	1,571	1	12	2