

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201508

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+06.00)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	600	CY	UNDERCUT EXCAVATION
0080000000-E	SP	600	TON	CLASS IV SUBGRADE STABILIZA- TION
0134000000-E	240	14	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	40	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	40	LF	15" SIDE DRAIN PIPE
0345000000-E	310	32	LF	24" SIDE DRAIN PIPE
0366000000-E	310	224	LF	15" RC PIPE CULVERTS, CLASS III
0378000000-E	310	44	LF	24" RC PIPE CULVERTS, CLASS III
0708000000-E	310	20	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1489000000-E	610	170	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	340	TON	ASPHALT CONC SURFACE COURSE, TYPE SP9.5A
1560000000-E	620	30	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2022000000-E	815	112	CY	SUBDRAIN EXCAVATION
2033000000-E	815	84	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS

ItemNumber	Sec #	Quantity	Unit	Description
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2286000000-N	840	5	EA	MASONRY DRAINAGE STRUCTURES
2355000000-N	840	4	EA	FRAME WITH GRATE, STD 840.29
2396000000-N	840	1	EA	FRAME WITH COVER, STD 840.54
2556000000-E	846	405	LF	SHOULDER BERM GUTTER
3030000000-E	862	350	LF	STEEL BM GUARDRAIL
3045000000-E	862	25	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3628000000-E	876	55	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	3	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	460	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4412000000-E	SP	230	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	56	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4446100000-E	SP	96	LF	BARRICADES (TYPE III)
4810000000-E	1205	2,600	LF	PAINT PAVEMENT MARKING LINES (4")
6000000000-E	1605	725	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	180	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	165	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1	ACR	TEMPORARY MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
6029000000-E	SP	185	LF	SAFETY FENCE
6030000000-E	1630	210	CY	SILT EXCAVATION
6036000000-E	1631	725	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
6084000000-E	1660	1	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.1	ACR	REFORESTATION

5/28/99
03-NOV-2004 10:32
R:\Roadway\PC\B4180_rdy_tsh.dgn
MRHussey AT