

PROJECT NO.	SHEET NO.	TOTAL NO.
10CR.10601.3, etc	11	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LENGTH MI	WIDTH FT	TRAFFIC CONTROL LS	INCIDENTAL STONE BASE TONS	SHOULDER CONSTRUCTION SMI	SHOULDER RECONSTRUCTION SMI	1 1/2" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0C TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	6" DRIVEWAYS SY	DROP INLET ADJ. EA	MANHOLES ADJ. EA	METER OR VALVE BOX ADJ. EA	TEMPORARY SILT FENCE LF	STONE FOR EROSION CONTROL, CLASS R TN	SEDIMENT CONTROL STONE TN	SEED & MULCHING AC	
10CR.10601.3	Mecklenburg	1	NC 160 (STEELE CREEK RD.)	FROM ERWIN RD. (SR 1120) TO PVT JOINT @ NC 49	1	0.84	24		25		1.68		133		1,117	250		83	250			2	3				1.0	
TOTAL FOR PROJ NO. 10CR.10601.3						0.84			25		1.68		133		1,117	250		83	250			2	3				1.0	
10CR.306003.15	Mecklenburg	2	NC 160 (STEELE CREEK RD.)	FROM PVT JOINT @ SHOPTON RD. W (SR 1116) TO WESTINGHOUSE BLVD. (SR 1410)	1,2	1.7	22		51		3.40		122		2,370	600		181	600				1				2.1	
TOTAL FOR PROJ NO. 10CR.306003.15						1.7			51		3.40		122		2,370	600		181	600					1				2.1
10CR.306003.16	Mecklenburg	3	NC 160 (STEELE CREEK RD.)	FROM WESTINGHOUSE BLVD. (SR 1410) TO ERWIN RD. (SR 1120)	1,2	1.26	22		38		2.52		122		1,793	450		137	450			1	2				1.5	
TOTAL FOR PROJ NO. 10CR.306003.16						1.26			38		2.52		122		1,793	450		137	450				1	2				1.5
10CR.306007.7	Mecklenburg	4	RAMAH CH RD. (SR 2439)	FROM NC 115 TO ECL HUNTERSVILLE	3	1.1	20		33		2.20		120		1,239	350		97	350								1.3	
TOTAL FOR PROJ NO. 10CR.306007.7						1.1			33		2.20		120		1,239	350		97	350									1.3
10CR.306003.17	Mecklenburg	5	NC 24 WB (ALBEMARLE RD.)	FROM REGAL OAKS TO REDDMAN RD.	5	1.12	36	0.5				23,654			2,412			145	400									
TOTAL FOR PROJ NO. 10CR.306003.17						1.12			0.5			23,654			2,412			145	400									
10CR.306003.18	Mecklenburg	6	E. 7TH ST. (SR 3300)	FROM US 74 TO LAUREL AVE.	6	0.9	36	0.5				20,000			1,770			106	350			15	15					
TOTAL FOR PROJ NO. 10CR.306003.18						0.9			0.5			20,000			1,770			106	350				15	15				
10CR.20601.19	Mecklenburg	7	SLEDGE RD. (SR 1119)	FROM WINGET RD. (SR 1117) TO NC 160 (STEELE CREEK RD.)	7,8	0.6	20		18	1.20			111	520	749	225	22	60	225	35	1		1	100	60	30	1.5	
TOTAL FOR PROJ NO. 10CR.20601.19						0.6				18	1.20		111	520	749	225	22	60	225	35	1		1	100	60	30	1.5	
10CR.20601.20	Mecklenburg	8	CAPP HILL MINE RD. (SR 2050)	FROM BEATTIES FORD RD. (SR 2074) TO NCL CHARLOTTE	9 TO 11	0.6	32		18	0.16	0.53		178	80	1,040	225	3	77	225	105		1	2	100	60	30	1.5	
TOTAL FOR PROJ NO. 10CR.20601.20						0.6				18	0.16	0.53		178	80	1,040	225	3	77	225	105		1	2	100	60	30	1.5
10CR.20601.21	Mecklenburg	9	E. JOHN ST. (SR 1010)	FROM PVT JOINT @ I-485 TO UNION CO. LINE	4	0.77	24		30		1.54		133		1,004	400		86	500							0.9		
TOTAL FOR PROJ NO. 10CR.20601.21						0.77				30	1.54		133		1,004	400		86	500								0.9	
GRAND TOTAL						8.89			1	213	1.36	11.87	43,654	919	600	13,494	2,500	25	972	3,350	140	1	19	24	200	120	60	9.8