

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	450 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	9 SMI		
0004	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,287 TON		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,427 TON		
0006	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	510 TON		
0007	2612000000-E	848	6" CONCRETE DRIVEWAY	60 SY		
0008	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0009	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	48,420 LF		
0010	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	29,700 LF		
0011	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	297 EA		
0012	6000000000-E	1605	TEMPORARY SILT FENCE	200 LF		
0013	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10 TON		
0014	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		

0938/Oct13/Q89377.5/D44854100000/E14

Total Amount Of Bid For Entire Project :

**Contract No: C 201655**

**County: Perquimans**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General