

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	51 TON		
0005	0343000000-E	310	15" SIDE DRAIN PIPE	300 LF		
0006	0995000000-E	340	PIPE REMOVAL	414 LF		
0007	1245000000-E	SP	SHOULDER RECONSTRUCTION	19.2 SMI		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO *****" DEPTH (0" TO 3")	2,667 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	1,800 SY		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,811 TON		
0011	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	28,330 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	17,273 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,746 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	695 TON		
0015	2253000000-E	840	PIPE COLLARS	1 CY		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0017	4430000000-N	1130	DRUMS	80 EA		
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	121,256 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	100,706 LF		
0020	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,050 LF		
0021	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0022	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	29 EA		
0023	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	98,580 LF		
0024	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,200 LF		
0025	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC-TER	32 EA		
0026	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	29 EA		
0027	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,130 EA		
0028	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	45 TON		
0029	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0030	6084000000-E	1660	SEEDING & MULCHING	37.8 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0031	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
AA1						
0032	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	132 LF		
AA1						
*** OR ***						
0033	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	128 LF		
AA2						
0034	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	40 LF		
AA2						

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	4 LF		
----- *** OR *** -----						
0036 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	128 LF		

0037 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	40 LF		

0038 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	4 LF		

***** END SCHEDULE AA *****						
0743/Oct26/Q387864.0/D92421100000/E38			Total Amount Of Bid For Entire Project :			

Contract No: C 201260

County: Pitt

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General