

PROJECT NO.	SHEET NO.	TOTAL NO.
13CR.10111.5, ETC.	3	7

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENT. STONE BASE TONS	3" MILLING SY	3" TO 4.5" MILLING SY	0" TO 1.5" MILLING SY	INTER-MEDIATE COURSE, 119.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	PG 64-22 PLANT MIX TONS	WHEEL-CHAIR RAMPS EA	DROP INLET EA	MANHOLES EA	METER OR VALVE BOX EA
13CR.10111.5	Buncombe	1	NC 63	SR 1004 TO SR 1615	1	4.46	24	223					6,609		397				
		2	US 19/23	SR 1233 TO NC 112	2	0.61	60			400	8,589	80	2,186		131				
<b>TOTAL FOR PROJ NO. 13CR.10111.5</b>						<b>5.07</b>		<b>223</b>		<b>400</b>	<b>8,589</b>	<b>80</b>	<b>8,795</b>		<b>528</b>				
13CR.20111.3	Buncombe	3	SR 1394	SR 1392 TO END OF PAVEMENT	3	2.4	18	120						2,943	191				
		4	SR 2435	BLACK MT. WCL TO OWEN MIDDLE SCHOOL	3	0.8	24	40						1,295	84				2
		5	SR 2474	SR 3435 TO BLACK MT. CITY LIMITS	3	3.4	19	170						4,244	276				
		6	SR 1607	SR 1604 TO MADISON COUNTY	3	1.5	20	75						1,680	109				
<b>TOTAL FOR PROJ NO. 13CR.20111.3</b>						<b>8.1</b>		<b>405</b>						<b>10,162</b>	<b>660</b>				<b>2</b>
13CR.301102.5	Buncombe	7	US 19/23	NC 112 TO BEGIN CONC. PAVEMENT	2	1.29	60			600	17,563	115	4,595		275			5	
		8	US 19/23 BUSINESS	I-240 TO SR 3412	5	0.7	45		18,480					1,885	123	30		27	5
		9	US 25 (MERRIMON AVENUE)	MARCELLUS TO CHATHAM	4	1.1	40				12,907			2,669	173	40	5	25	9
<b>TOTAL FOR PROJ NO. 13CR.301102.5</b>						<b>3.09</b>			<b>18,480</b>	<b>600</b>	<b>30,470</b>	<b>115</b>	<b>4,595</b>	<b>4,554</b>	<b>571</b>	<b>70</b>	<b>5</b>	<b>57</b>	<b>14</b>
<b>GRAND TOTAL</b>						<b>16.26</b>		<b>628</b>	<b>18,480</b>	<b>1,000</b>	<b>39,059</b>	<b>195</b>	<b>13,390</b>	<b>14,716</b>	<b>1,759</b>	<b>70</b>	<b>5</b>	<b>57</b>	<b>16</b>

## THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	4685000000-E	4686000000-E	4697000000-E	4710000000-E	4721000000-E	4725000000-E					4810000000-E	4835000000-E	4840000000-N			
					4" X 90 M THERMO LF	4" X 120 M THERMO LF	8" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO LT STR RT ARROW 90 M EA	4" PAINT LF	24" WHITE PAINT LF	PAINT MSG SCHOOL EA			
13CR.10111.5	Buncombe	1	NC 63	SR 1004 TO SR 1615	47,990	47,990														
		2	US 19/23	SR 1233 TO NC 112		9,662		108		4	4	4								
<b>TOTAL FOR PROJ NO. 13CR.10111.5</b>					<b>47,990</b>	<b>57,652</b>		<b>108</b>		<b>4</b>	<b>4</b>	<b>4</b>								
13CR.20111.3	Buncombe	3	SR 1394	SR 1392 TO END OF PAVEMENT														101,376		
		4	SR 2435	BLACK MT. WCL TO OWEN MIDDLE SCHOOL														33,792	48	6
		5	SR 2474	SR 3435 TO BLACK MT. CITY LIMITS														143,616		
		6	SR 1607	SR 1604 TO MADISON COUNTY														63,360		
<b>TOTAL FOR PROJ NO. 13CR.20111.3</b>																		<b>342,144</b>	<b>48</b>	<b>6</b>
13CR.301102.5	Buncombe	7	US 19/23	NC 112 TO BEGIN CONC. PAVEMENT		20,434														
		8	US 19/23 BUSINESS	I-240 TO SR 3412		7,392		1,000		6	3							4,000		
		9	US 25 (MERRIMON AVENUE)	MARCELLUS TO CHATHAM		14,520	1,200	360	12			4	1	10						
<b>TOTAL FOR PROJ NO. 13CR.301102.5</b>						<b>42,346</b>	<b>1,200</b>	<b>1,360</b>	<b>12</b>	<b>6</b>	<b>3</b>	<b>4</b>	<b>1</b>	<b>10</b>				<b>4,000</b>		
<b>GRAND TOTAL</b>					<b>47,990</b>	<b>99,998</b>	<b>1,200</b>	<b>1,468</b>	<b>12</b>	<b>10</b>	<b>7</b>	<b>8</b>	<b>1</b>	<b>10</b>				<b>346,144</b>	<b>48</b>	<b>6</b>