

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,052 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	88.06 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4-1/2")	3,755 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	26,283 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	350 TON		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	500 TON		
0008	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	642 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	16,083 TON		
001C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	18,317 TON		
0011	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	32,888 TON		
0012	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	207 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,085 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,100 TON		
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	225 TON		
0016	2830000000-N	858	ADJUSTMENT OF MANHOLES	39 EA		

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	34	EA	
001E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	213,000	LF	
001S	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	149,285	LF	
002C	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	737	LF	
0021	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,550	LF	
0022	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	150	LF	
0023	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,295	LF	
0024	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	84	EA	
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	368	EA	
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	527,800	LF	
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	170	LF	
002E	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	4,388	EA	
002E	6084000000-E	1660	SEEDING & MULCHING	119	ACR	
003C	7288000000-E	1715	TRENCHING (PAVED)	300	LF	
0031	7300000000-E	1715	TRENCHING (UNPAVED)	900	LF	
0032	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	12	EA	
003C	7420000000-E	1722	2" RISER WITH WEATHERHEAD	11	EA	

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	8,015	LF	
0035	7456000000-E	1726	LEAD-IN CABLE	900	LF	
0036	7990000000-E	SP	GENERIC SIGNAL ITEM (1") PVC CONDUIT	300	LF	
0037	7990000000-E	SP	GENERIC SIGNAL ITEM (2") PVC CONDUIT	1,100	LF	
0827/Jan20/Q1015133.06/D144621200000/E37			Total Amount Of Bid For Entire Project :			

C201553
COUNTIES: CUMBERLAND & HARNETT

2/16/99

Contract No: C201553
Counties: Cumberland & Harnett

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General