

PROJECT NO.	SHEET NO.	TOTAL NO.
37671, ETC	7	15

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	1½" MILLING IN BUNN SY	2.5" MILLING SY	1½" MILLING UNDER BRIDGE SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	INTER-MEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	WHEEL-CHAIR RAMPS EA	MANHOLES EA	METER OR VALVE BOX EA	INDUCTIVE LOOP LF
37671	Franklin	1	NC 39	LOUISBURG CITY LIMITS TO NC 98	7,8	9.3	24	465	4,500	7,100			10,000		1,050	11,786		756			4	1	
TOTAL FOR PROJ NO. 37671						9.3		465	4,500	7,100			10,000		1,050	11,786		756			4	1	
5CR.10351.5	Franklin	2	NC 56	FROM EAST CITY LIMIT OF FRANKLINTON TO SR 1114 (PEACH ORCHARD ROAD)	7	4.6	24	110					1,500			5,469		328					
TOTAL FOR PROJ NO. 5CR.10351.5						4.6		110	0	0			1,500		0	5,469		328					
5CR.20351.5	Franklin	3	SR 1139 SID MITCHELL ROAD	FROM NC 96 TO SR 1140 (JOHN MITCHELL ROAD)	1	1.35	24	32						1,341			1,312	143	100				
		4	SR 1139 SID MITCHELL ROAD	FROM SR 1140 (JOHN MITCHELL ROAD) TO SR 1147 (HOLDEN ROAD)	2	2.07	24	50									2,012	131	75				
		5	SR 1425 (WHITE LEVEL ROAD)	FROM SR 1421 (HICKORY ROCK ROAD) TO SR 1459 (WOOD ROAD)	3	5.3	20	127						90			4,298	283	400				
		6	SR 1243 (WALTER GRISSOM ROAD)	FROM SR 1003 (SIMS BRIDGE ROAD) TO 0.5 MILE NORTH OF SR 1244 (GEN GREEN ROAD)	4	1.6	18	38									1,168	76	100				
		7	SR 1433 (PERSON ROAD)	FROM SR 1432 (HARRIS JONES ROAD) TO SR 1434 (GOLD SAND ROAD)	4	2.4	19	58									1,849	120	200				
TOTAL FOR PROJ NO. 5CR.20351.5						12.72		305	0	0			0	1,431	0		10,639	753	875				
5CR.303506.5	Franklin	8	NC 56	FROM JOINT APPROX. 0.25 MILE WEST OF US 1 TO US 1A	5,6	0.7	36				1,900	1,700	120			1,246		75		2	4	4	720
TOTAL FOR PROJ NO. 5CR.303506.5						0.7		0	0	0	1,900	1,700	120	0	0	1,246		75		2	4	4	720
GRAND TOTAL						27.32		880	4,500	7,100	1,900	1,700	11,620	1,431	1,050	18,501	10,639	1,912	875	2	8	5	720