

PROJECT NO.	SHEET NO.	TOTAL NO.
12CR.10551.3, ETC.	4	7

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECON-STRUCTION SMI	1½" MILLING SY	INCIDENTAL MILLING SY	INTER. COURSE, 19.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	AST MAT COAT #6 SY	MANHOLES EA	METER OR VALVE BOX EA	PORTABLE LIGHTING LS				
12CR.301816.3	Catawba	1	SR 1306 (2ND AVE NE)	FROM US 321 TO NC 127	3	0.13	24																	
					4	0.24	36																	
					5	0.86	30																	
					6	0.44	VAR. 13-32	20				31,000				3,875	775	279	580	31,000	54	23	Lump Sum	
TOTAL FOR PROJ NO. 12CR.301816.3						1.67		20		31,000		3,875	775	279	580	31,000	54	23	Lump Sum					
12CR.20181.4	Catawba	2	SR 2687	FROM 1841 TO SR 2688	1	0.22	18	11					220	11	14	22								
			3	SR 2688	FROM DEAD END TO DEAD END	1	0.4	18	39					360	13	22	26							
		4	SR 2019	FROM SR 1008 TO NEW PAVEMENT	7	0.57	22	75				1,164	692	35	98	210								
TOTAL FOR PROJ NO. 12CR.20181.4						1.19		125		0	1,164	1,272	59	134	258									
12CR.10551.3	Lincoln	5	NC 182	FROM NC 27 TO SR 1002	2	5.74	20	400	11.5		450		6,262	500	406	1,000								
TOTAL FOR PROJ NO. 12CR.10551.3						5.74		400	11.5	0	450	0	6,262	500	406	1,000								
12CR.20551.4	Lincoln	6	SR 1524	FROM SR 1377 TO SR 1524	1	0.66	18	33					649	33	41	65								
			7	SR 1390	FROM SR 1439 TO DEAD END	1	0.97	18	48					953	48	60	95							
			8	SR 1883	FROM SR 1397 TO CUL-DE-SAC	1	0.27	18	14					265	13	17	27							
			9	SR 1941	FROM SR 1397 TO DEAD END	1	0.42	20	21					458	23	29	46							
		10	SR 1373	FROM NC 16 TO CATAWBA COUNTY LINE	1	2.09	22	104						2,507	125	158	250							
TOTAL FOR PROJ NO. 12CR.20551.4						4.41		220	0	0	0	0	4,832	242	305	483								
GRAND TOTAL						13.01		765	11.5	31,000	450	1,164	16,241	1,576	1,124	2,321	31,000	54	23	Lump Sum				