

PROJECT NO. 8CR.10771.5, 8CR.20771.5 8CR.307716.5, 8CR.307718.5	SHEET NO. 3	TOTAL NO.
---	-----------------------	-----------

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	4" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ADJUST DROP INLET/CATCH BASIN EA	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	SEED & MULCHING AC
8CR.10771.5	Richmond	1	US 220 SBL	FROM SR 1301 TO SR 1327	3,7	0.8	24-56	50	1.6	15770	200	2250	1530	1310	106	92	25				1.20
		2	US 74 BUS. EBL	FROM ECL OF ROCKINGHAM TO WCL OF HAMLET	4,5	0.73	26-40	50	1.46		200		1300			79	25				1.10
		3	US 74 BUS. WBL	FROM WCL OF HAMLET TO ECL OF ROCKINGHAM	4,5	0.73	26-40	50	1.46		200		1300			78	25				1.10
TOTAL FOR PROJ NO. 8CR.10771.5						2.26		150	4.52	15770	600	2250	4140	1300	106	249	75				3.40
8CR.20771.5	Richmond	4	SR 1155	FROM NC 73 TO SR 1148	1	2.32	18	116	4.64		1000		2935		176		25				3.40
		5	SR 1004	FROM NCL OF HOFFMAN TO MOORE CO.	2	1.37	18-20	69	2.74		200		1285		77		25				2.00
TOTAL FOR PROJ NO. 8CR.20771.5						3.69		185	7.38	0	1200	0	4220	0	253	0	50				5.40
8CR.307716.5	Richmond	6	NC 177	FROM WALNUT STREET TO SR 1903	4,5,6	0.51	24-34	15	0.9		200		715		43			2	5	7	0.65
TOTAL FOR PROJ NO. 8CR.307716.5						0.51		15	0.9	0	200	0	715	0	43			2	5	7	0.65
8CR.307718.5	Richmond	7	SR 1004	FROM US 1 TO WCL OF HOFFMAN	2	1	18-20	50	2		200		940		56		25				1.50
TOTAL FOR PROJ NO. 8CR.307718.5						1		50	2	0	200	0	940	0	56	0	25				1.50
GRAND TOTAL						7.46		400	14.8	15770	2200	2250	5160	4855	415	292	150	2	5	7	10.95