



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

February 14, 2006

Addendum No. 1

RE: Contract ID: C201562

WBS# 37017

Wake County

Bridge over Richland Creek and
Approaches on SR-1930 (Stadium Drive).

February 21, 2006 Letting

To Whom It May Concern:

Reference is made to the plans and proposal form recently furnished to you on this project.

The following revision has been made to the proposal.

On Page No. 33, the project special provision entitled "Utility Conflicts (Contractor)" has been revised and the project special provision entitled "Utility Construction" has been added. Please void Page No. 33 in your proposal and staple the revised Page No. 33 thereto.

On Page No. 64 the "BASIS OF PAYMENT" has been revised. Please void Page No. 64 in your proposal and staple the revised Page No. 64 thereto.

On Page No. 2 of the item sheets the following new line items are hereby added: "32-5912000000-E-SP-8" Sanitary Line (Lump Sum) and "33-5912000000-E SP 12" water line (Lump Sum). The Contractor's bid price shall include these two new pay items. The Contract will be prepared accordingly.

The following revisions have been made to the plans.

Plan Sheet No. 2-A has been added. Please insert Plan Sheet No. 2-A after Plan Sheet No. 2 in your plans.

Plan Sheet No. U-1 And W-01 have been added. Please insert Plan Sheet No. U-1 And W-01 after Plan Sheet No. E-3 in your plans.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
DESIGN SERVICES UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119

WEBSITE: WWW.DOH.DOT.STATE.NC.US

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B2
1020 BIRCH RIDGE DRIVE
RALEIGH NC

Page No. 2
Wake County (C201562)

Plan Sheet No. S-1 has been revised. Please void Plan Sheet No. S-1 in your plans and staple the revised Plan Sheet No. S-1 thereto.

The Expedite file has been updated to reflect these revisions. Please download the Expedite addendum file and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE
Contract Officer

RAG/jag/pa

cc: Mr. W. S. Varnedoe, PE
Mr. S. D. DeWitt, PE
Mr. E. C. Powell, PE
Mr. J. G. Nance, PE
Ms. D. M. Barbour, PE
Mr. Art McMillan, PE
Mr. Victor Barbour, PE
Mr. John Emerson, PE
Mr. Mark Staley (2)
Mr. Robert Memory
Mr. R. E. Davenport, Jr., PE
Ms. Marsha Byrd
Ms. Taylor Mishoe
Project File (2)

Contract C201562

Wake County

UTILITY CONFLICTS (DEPARTMENT):

The Department will be responsible for the adjustment of any utility at the bridge site prior to the date of availability.

UTILITY CONFLICTS (CONTRACTOR):

The Contractor will be responsible for contacting Progress Energy for de-energizing the overhead power lines. The power lines can be de-energized for two (2) one continuous Monday through Friday five (5) day periods. The power lines shall not be de-energized after May 31, 2006. The Contractor shall contact Baxter Matheson with Progress Energy at 919-546-6709 one- (1) week before beginning pile driving and cored slab operations.

ASPHALT BINDER FOR ASPHALT CONCRETE:

There will be no separate measurement or payment for asphalt binder required for asphalt concrete. Payment for the various types of asphalt concrete will be full compensation for the asphalt binder required for each mix type.

Utility Construction

The work of this provision consists of replacing an existing sanitary sewer with a new sanitary sewer and providing a new water line for future use.

All work and materials shall conform to the plans, the City of Raleigh requirements for water and sewer, the NCDOT 2002 Standard Specifications, and the appropriate DENR regulations.

The existing sanitary sewer line shall be properly abandoned.

The sanitary sewer line will be measured and paid for as a lump sum item. Such costs shall include excavation, trenchless excavation, foundation conditioning, furnishing and installing all materials, testing, cleaning, bedding, backfilling, abandonment of existing facilities, and incidentals to complete the work.

The water line will be measured and paid for as a lump sum item. Such costs shall include excavation, trenchless excavation, foundation conditioning, furnishing and installing all materials, testing, cleaning, sterilizing, bedding, backfilling, and incidentals to complete the work.

Payment will be made under:

8" Sanitary Sewer

Lump Sum

12" Water Line

Lump Sum

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

Temporary Seeding:

Fertilizer shall be the same analysis as specified for "Seeding and Mulching" and applied at the rate of 400 pounds (450kg) and seeded at the rate of 50 pounds per acre (55kg per hectare). Kobe or Korean Lespedeza, German Millet, or Browntop Millet shall be used in summer months and rye grain during the remainder of the year. The Engineer will determine the exact dates for using each kind of seed.

Fertilizer Topdressing:

Fertilizer used for topdressing shall be 16-8-8 grade and shall be applied at the rate of 500 pounds per acre (560 kg per hectare). Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 2-1-1 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as 16-8-8 analysis.

Supplemental Seeding:

The kinds of seed and proportions shall be the same as specified for "Seeding and Mulching", and the rate of application may vary from 25# to 75# per acre (28kg to 85kg per hectare). The actual rate per acre (hectare) will be determined by the Engineer prior to the time of topdressing and the Contractor will be notified in writing of the rate per acre (hectare), total quantity needed, and areas on which to apply the supplemental seed. Minimum tillage equipment, consisting of a sod seeder shall be used for incorporating seed into the soil as to prevent disturbance of existing vegetation. A clodbuster (ball and chain) may be used where degree of slope prevents the use of a sod seeder.

Mowing:

The minimum mowing height on this project shall be six inches (150 mm).

BASIS OF PAYMENT:

Except for temporary silt fence, payment for all erosion control, including seeding and mulching, temporary seeding, fertilizer topdressing, matting for Erosion Control and supplemental seeding will be included in the lump sum price bid for "Erosion Control."

Temporary silt fence will be paid for at the contract unit price per linear foot for "Temporary Silt Fence".