

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0022000000-E | 225 | UNCLASSIFIED EXCAVATION | 14,400 CY | | |
| 0004 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+03.50-L-) | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 100 CY | | |
| 0007 | 0063000000-N | SP | GRADING | Lump Sum | L.S. | |
| 0008 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZA- TION | 500 TON | | |
| 0009 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 50 CY | | |
| 0010 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 500 CY | | |
| 0011 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 500 SY | | |
| 0012 | 0199000000-E | SP | TEMPORARY SHORING | 1,280 SF | | |
| 0013 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 67 TON | | |
| 0014 | 0360000000-E | 310 | 12" RC PIPE CULVERTS, CLASS III | 8 LF | | |
| 0015 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 92 LF | | |
| 0016 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 104 LF | | |
| 0017 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 48 LF | | |
| 0018 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 120 LF | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0019 | 0714000000-E | 310 | 18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 192 LF | | |
| 0020 | 0720000000-E | 310 | 24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 28 LF | | |
| 0021 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 6 EA | | |
| 0022 | 0807000000-E | 310 | 18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK | 6 EA | | |
| 0023 | 0808000000-E | 310 | 24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK | 2 EA | | |
| 0024 | 0995000000-E | 340 | PIPE REMOVAL | 200 LF | | |
| 0025 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 1,100 TON | | |
| 0026 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 50 TON | | |
| 0027 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 270 TON | | |
| 0028 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 150 TON | | |
| 0029 | 1525000000-E | SP | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 880 TON | | |
| 0030 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 74 TON | | |
| 0031 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 30 TON | | |
| 0032 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 10 EA | | |
| 0033 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 225 CY | | |
| 0034 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 170 CY | | |
| 0035 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 1,000 LF | | |
| 0036 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 30 EA | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-----------|-----------|--------|
| 0037 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 2 EA | | |
| 0038 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 12 LF | | |
| 0039 | 2154000000-N | 820 | METAL FUNNELS | 1 EA | | |
| 0040 | 2165000000-E | 820 | 12" FUNNEL DRAIN PIPE | 24 LF | | |
| 0041 | 2176000000-E | 820 | 12" FUNNEL DRAIN PIPE ELBOWS | 2 EA | | |
| 0042 | 2190000000-N | 828 | TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE | 1 EA | | |
| 0043 | 2264000000-E | 840 | PIPE PLUGS | 1 CY | | |
| 0044 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 8 EA | | |
| 0045 | 2319000000-N | 840 | FRAME WITH GRATE, DETAIL 840.***** (840.16) | 1 EA | | |
| 0046 | 2366000000-N | 840 | FRAME WITH TWO GRATES, STD 840.24 | 2 EA | | |
| 0047 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 5 EA | | |
| 0048 | 2500000000-E | 842 | CONCRETE RETAINING WALLS | 15 CY | | |
| 0049 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 10 LF | | |
| 0050 | 2577000000-E | 846 | CONCRETE EXPRESSWAY GUTTER | 200 LF | | |
| 0051 | 2619000000-E | 850 | 4" CONCRETE PAVED DITCH | 115 SY | | |
| 0052 | 2724000000-E | 857 | PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED | 270 LF | | |
| 0053 | 3000000000-N | SP | IMPACT ATTENUATOR UNIT, TYPE 350 | 1 EA | | |
| 0054 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 400 LF | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|------------|-----------|--------|
| 0055 | 3045000000-E | 862 | STEEL BM GUARDRAIL, SHOP CURVED | 37.5 LF | | |
| 0056 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0057 | 3195000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE AT-1 | 1 EA | | |
| 0058 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 3 EA | | |
| 0059 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 3 EA | | |
| 0060 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 665 LF | | |
| 0061 | 3380000000-E | 862 | TEMPORARY STEEL BM GUARDRAIL | 675 LF | | |
| 0062 | 3387000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77) | 2 EA | | |
| 0063 | 3387000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III) | 4 EA | | |
| 0064 | 3389100000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY | 1 EA | | |
| 0065 | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (3) | 550 LF | | |
| 0066 | 3649000000-E | 876 | PLAIN RIP RAP, CLASS B | 50 TON | | |
| 0067 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 570 SY | | |
| 0068 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 3 EA | | |
| 0069 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (E) | 12.5 SF | | |
| 0070 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 54 LF | | |
| 0071 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 2 EA | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0072 | 4129000000-N | 906 | RELOCATE SIGN, TYPE ***** (E) | 1 EA | | |
| 0073 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 1 EA | | |
| 0074 | 4158000000-N | 907 | DISPOSAL OF SIGN SYSTEM, WOOD | 4 EA | | |
| 0075 | 4192000000-N | 907 | DISPOSAL OF SUPPORT, U-CHANNEL | 1 EA | | |
| 0076 | 4412000000-E | SP | WORK ZONE SIGNS (STATIONARY) | 128 SF | | |
| 0077 | 4412100000-E | SP | WORK ZONE SIGNS (PORTABLE) | 96 SF | | |
| 0078 | 4412200000-E | SP | WORK ZONE SIGNS (BARRICADE MOUNTED) | 52 SF | | |
| 0079 | 4430000000-N | 1130 | DRUMS | 55 EA | | |
| 0080 | 4446100000-E | SP | BARRICADES (TYPE III) | 64 LF | | |
| 0081 | 4450000000-N | 1150 | FLAGGER | 480 HR | | |
| 0082 | 4465000000-N | 1160 | TEMPORARY CRASH CUSHIONS | 2 EA | | |
| 0083 | 4490000000-E | 1170 | PORTABLE CONCRETE BARRIER (ANCHORED) | 230 LF | | |
| 0084 | 4495000000-E | 1170 | PORTABLE CONCRETE BARRIER (DRAINAGE) | 80 LF | | |
| 0085 | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 29 EA | | |
| 0086 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 16,576 LF | | |
| 0087 | 4847000000-E | SP | POLYUREA PAVEMENT MARKING LINES (4") | 4,620 LF | | |
| 0088 | 4905000000-N | 1253 | SNOWPLOWABLE PAVEMENT MARKERS | 29 EA | | |
| 0089 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 900 LF | | |
| 0090 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 115 TON | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0091 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 315 TON | | |
| 0092 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 325 TON | | |
| 0093 | 6015000000-E | 1615 | TEMPORARY MULCHING | 3.5 ACR | | |
| 0094 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 150 LB | | |
| 0095 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.5 TON | | |
| 0096 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 200 LF | | |
| 0097 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 2 EA | | |
| 0098 | 6029000000-E | SP | SAFETY FENCE | 1,540 LF | | |
| 0099 | 6030000000-E | 1630 | SILT EXCAVATION | 1,180 CY | | |
| 0100 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 1,200 SY | | |
| 0101 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 10 SY | | |
| 0102 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 500 LF | | |
| 0103 | 6070000000-N | SP | SPECIAL STILLING BASINS | 3 EA | | |
| 0104 | 6084000000-E | 1660 | SEEDING & MULCHING | 3.5 ACR | | |
| 0105 | 6087000000-E | 1660 | MOWING | 2 ACR | | |
| 0106 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0107 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0108 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 75 LB | | |
| 0109 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2.75 TON | | |
| 0110 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2.5 HR | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|---|--------------|-----------|--------|
| 0111 | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0112 | 6123000000-E | 1670 | REFORESTATION | 0.8 ACR | | |
| STRUCTURE ITEMS | | | | | | |
| 0113 | 8007000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+03.50 -L-) | Lump Sum | L.S. | |
| 0114 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+03.50 -L-) | Lump Sum | L.S. | |
| 0115 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+03.50 -L-) | Lump Sum | L.S. | |
| 0116 | 8105520000-E | SP | 3'-0" DIA DRILLED PIERS IN SO IL | 26.25 LF | | |
| 0117 | 8105620000-E | SP | 3'-0" DIA DRILLED PIERS NOT IN SOIL | 15 LF | | |
| 0118 | 8105640000-E | SP | 3'-6" DIA DRILLED PIERS NOT IN SOIL | 24.75 LF | | |
| 0119 | 8113000000-N | SP | SID INSPECTION | 1 EA | | |
| 0120 | 8115000000-N | SP | CROSSHOLE SONIC LOGGING | 2 EA | | |
| 0121 | 8121000000-N | SP | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+03.50 -L-) | Lump Sum | L.S. | |
| 0122 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 91.2 CY | | |
| 0123 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (17+03.50 -L-) | Lump Sum | L.S. | |
| 0124 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 17,030 LB | | |

County : Alleghany

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|---|--------------|-------|--|----------------|-----------|--------|
| 0125 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 2,226 LB | | |
| 0126 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 324.52 LF | | |
| 0127 | 8608000000-E | 876 | PLAIN RIP RAP CLASS II (2'-0" THICK) | 145 TON | | |
| 0128 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 161 SY | | |
| 0129 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0130 | 8753200000-E | SP | 3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS | 1,784.86 LF | | |
| 0755/Feb10/Q76779.38/D501435980000/E130 | | | Total Amount Of Bid For Entire Project : | | | |

C201399 (B-4007)
COUNTY: Alleghany

2/16/99

Contract No: C201399
County: Alleghany

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General