

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,300 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (10+62.50)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0009	0098000000-E	228	PRE-SPLITTING OF ROCK	600 SY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	525 SF		
0013	0245000000-E	SP	GENERIC GRADING ITEM ADDITIONAL GROUT FOR ROCK BOLT	35 GAL		
0014	0257000000-E	SP	GENERIC GRADING ITEM TYPE I ROCK BOLT	200 LF		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	13 TON		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	120 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1121000000-E	520	AGGREGATE BASE COURSE	25 TON		
001E	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	130 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	255 TON		
0022	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	90 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	27 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
002E	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
003C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0032	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	175 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0037	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (SPECIAL)	1	EA	
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0039	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1	EA	
004C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	250	LF	
0041	3635000000-E	876	PLAIN RIP RAP, CLASS II	25	TON	
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	300	SY	
0043	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
0044	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	12.5	SF	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	27	LF	
0046	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	
0047	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	8	EA	
004E	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	244	SF	
0049	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	208	SF	
005C	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	26	SF	
0051	4425000000-N	1125	WARNING FLAG SETS	2	EA	
0052	4430000000-N	1130	DRUMS	35	EA	
0053	4435000000-N	1135	CONES	35	EA	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4446100000-E	SP	BARRICADES (TYPE III)	36 LF		
0055	4455000000-N	1150	FLAGGER	60 MD		
0056	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0057	4485000000-E	1170	PORTABLE CONCRETE BARRIER	120 LF		
0058	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	18 EA		
0059	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,746 LF		
0060	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,746 LF		
0061	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	12 LF		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,256 LF		
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	36 LF		
0064	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,400 LF		
0065	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	22 EA		
0066	6000000000-E	1605	TEMPORARY SILT FENCE	600 LF		
0067	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0068	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	185 TON		
0069	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0070	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0071	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0073	6029000000-E	SP	SAFETY FENCE	300	LF	
0074	6030000000-E	1630	SILT EXCAVATION	410	CY	
0075	6036000000-E	1631	MATTING FOR EROSION CONTROL	625	SY	
0076	6042000000-E	1632	1/4" HARDWARE CLOTH	25	LF	
0077	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
007E	6087000000-E	1660	MOWING	0.5	ACR	
0079	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
008C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	
0083	6114000000-N	SP	SPECIALIZED HAND MOWING	0.5	HR	
0084	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
008E	6123000000-E	1670	REFORESTATION	0.1	ACR	
0086	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	35	SY	

STRUCTURE ITEMS

0087	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (10+63.50 -L-)	Lump Sum	L.S.	
008E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10+63.50 -L-)	Lump Sum	L.S.	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	21 LF		
009C	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	58.75 LF		
0091	8113000000-N	SP	SID INSPECTION	4 EA		
0092	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0093	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,339 SF		
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	2,521 SF		
009E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	104.6 CY		
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (10 + 63.50 -L-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,978 LB		
009E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,159 LB		
009E	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	52,480 LS		
010C	8468000000-E	460	ONE BAR METAL RAIL	133.98 LF		
0101	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-0" X 1'-6")	149.69 LF		
0102	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	170 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	189 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
010E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

C201571
COUNTY: Ashe

2/16/99

Contract No: C201571
County: Ashe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General