

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201484

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+92.00-L)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	600	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0106000000-E	230	2,100	CY	BORROW EXCAVATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	10	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0708000000-E	310	92	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	8	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1489000000-E	610	588	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	330	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	48	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	25	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2022000000-E	815	22	CY	SUBDRAIN EXCAVATION
2033000000-E	815	17	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	100	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	575	LF	SHOULDER BERM GUTTER

ItemNumber	Sec #	Quantity	Unit	Description
3030000000-E	862	637.5	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3649000000-E	876	15	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	262	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	192	SF	WORK ZONE SIGNS (STATIONARY)
4412000000-E	SP	69	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4430000000-N	1130	20	EA	DRUMS
4435000000-N	1135	20	EA	CONES
4446100000-E	SP	96	LF	BARRICADES (TYPE III)
4810000000-E	1205	7,200	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	12	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	730	LF	TEMPORARY SILT FENCE
6006000000-E	1610	50	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	90	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	45	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	120	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	500	LF	SAFETY FENCE
6030000000-E	1630	95	CY	SILT EXCAVATION

ItemNumber	Sec #	Quantity	Unit	Description
6036000000-E	1631	135	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH
6048000000-E	SP	125	SY	FLOATING TURBIDITY CURTAIN
6084000000-E	1660	2	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

24-JAN-2006 15:13  
 F:\p000000\proj\B4224.rdlj.sum\_3.dgn  
 \$\$\$USERNAME\$\$\$

5/28/99