

County : Duplin, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+92.00-L-)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	2,100 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
001C	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	92 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	588 TON		
0013	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	330 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	48 TON		
0015	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0016	2022000000-E	815	SUBDRAIN EXCAVATION	22 CY		
0017	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
001E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
002C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	575 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	637.5 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3649000000-E	876	PLAIN RIP RAP, CLASS B	15 TON		
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	262 SY		
0031	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	192 SF		
0032	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	69 SF		
003E	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0034	4430000000-N	1130	DRUMS	20 EA		
003E	4435000000-N	1135	CONES	20 EA		
003E	4446100000-E	SP	BARRICADES (TYPE III)	96 LF		

County : Duplin, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200	LF	
003E	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	12	EA	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	730	LF	
004C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50	TON	
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90	TON	
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	45	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	120	LF	
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
004E	6029000000-E	SP	SAFETY FENCE	500	LF	
004E	6030000000-E	1630	SILT EXCAVATION	95	CY	
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	135	SY	
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	80	LF	
0052	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	125	SY	
005E	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0054	6087000000-E	1660	MOWING	1	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	

County : Duplin, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
006C	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	

STRUCTURE ITEMS

0061	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+62.50-L)	Lump Sum	L.S.	
0062	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+62.50-L)	Lump Sum	L.S.	
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+62.50-L)	Lump Sum	L.S.	
0064	8364000000-E	450	HP12X53 STEEL PILES	490	LF	
006E	8384000000-E	450	HP14X73 STEEL PILES	543	LF	
006E	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (17+62.50-L)	Lump Sum	L.S.	
0067	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	372	TON	
006E	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
006E	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
007C	8990000000-N	SP	CONTRACT TIME	800	DOL	

C201484
COUNTY: Pender/Duplin

2/16/99

Contract No: C201484
County: Pender/Duplin

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General