

PROJECT: B-3445
COUNTY: Currituck

81

PROJECT SPECIAL PROVISIONS

Utility

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. Dominion Virginia Power
- B. Verizon
- C. Cox Communications

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A. Dominion Virginia Power

1. See "Utility By Others Plans" for utility conflicts.
2. The two temporary joint use poles on the south side of the bridge will be installed and utility lines relocated prior to the Date of Availability.
3. The two new permanent joint use poles on the north side of the bridge will be installed after rough grading is complete. The utility requires 4 weeks notice to begin construction, and 2 weeks to complete construction.
4. Conductors will be relocated to the permanent poles after completion of Phase II of the project, and the existing poles on the south side of the bridge will be removed. The utility requires 4 weeks notice to begin construction, and 2 weeks to complete construction.
5. The utility will require 2 weeks notice to begin construction and 1 week to complete construction for each crossing if the power lines at any of the seven pipe crossings are required to be de-energized.

B. Verizon

1. See "Utility By Others Plans" for utility conflicts.

PROJECT: B-3445
COUNTY: Currituck

2. All facilities will be relocated to the existing poles and the two temporary joint use poles on the south side of the bridge prior to the Date of Availability.
3. All facilities will be relocated to the permanent poles after completion of Phase II of the project. The utility requires 2 weeks notice to begin construction, and 2 weeks to complete construction.
4. The utility will require 2 weeks notice to begin construction and 2 weeks to complete construction at each of the 7 pipe crossings.

C. Cox Communications

1. See "Utility By Others Plans" for utility conflicts.
2. All facilities will be relocated to the existing poles and the two temporary joint use poles on the south side of the bridge prior to the Date of Availability.
3. All facilities will be relocated to the permanent poles after completion of Phase II of the project. The utility requires 2 weeks notice to begin construction, and 2 weeks to complete construction.