

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	20 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (24 + 18 -L-)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	500 CY		
0008	0106000000-E	230	BORROW EXCAVATION	3,500 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,300 SY		
0010	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	725 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0013	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	2,540 SF		
0014	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABIL- IZATION	2,400 SY		
0015	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VI)	600 TON		
0016	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VII)	1,725 TON		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	46 TON		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	112 LF		
001E	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (36", 0.075")	320 LF		
002C	0995000000-E	340	PIPE REMOVAL	80 LF		
0021	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0022	1121000000-E	520	AGGREGATE BASE COURSE	255 TON		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		
0024	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	680 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	70 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	85 TON		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	280 LF		
003C	3030000000-E	862	STEEL BM GUARDRAIL	625 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	287.5 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	2 EA		
003E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0037	3649000000-E	876	PLAIN RIP RAP, CLASS B	5 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,160 SY		
003E	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	128 SF		
004C	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	192 SF		
0041	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	70 SF		
0042	4430000000-N	1130	DRUMS	30 EA		
0043	4435000000-N	1135	CONES	30 EA		
0044	4446100000-E	SP	BARRICADES (TYPE III)	80 LF		
004E	4450000000-N	1150	FLAGGER	128 HR		
004E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0047	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4 EA		
004E	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	2 EA		
004E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,204 LF		
005C	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	995 LF		
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,896 LF		
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,800 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	282	LF	
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,850	LF	
0055	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	48	LF	
0056	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	900	LF	
0057	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	24	LF	
0058	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	35	EA	
0059	6000000000-E	1605	TEMPORARY SILT FENCE	985	LF	
0060	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	155	TON	
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	300	TON	
0063	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0065	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0066	6029000000-E	SP	SAFETY FENCE	300	LF	
0067	6030000000-E	1630	SILT EXCAVATION	370	CY	
0068	6036000000-E	1631	MATTING FOR EROSION CONTROL	525	SY	
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	835	LF	
0070	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	107	SY	

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0072	6087000000-E	1660	MOWING	0.5 ACR		
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0077	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0078	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		
0079	7060000000-E	1705	SIGNAL CABLE	1,300 LF		
0080	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4 EA		
0081	7252000000-E	1710	MESSENGER CABLE (1/4")	70 LF		
0082	7264000000-E	1710	MESSENGER CABLE (3/8")	1,180 LF		
0083	7300000000-E	1715	TRENCHING (UNPAVED)	80 LF		
0084	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2 EA		
0085	7360000000-N	1720	WOOD POLE	8 EA		
0086	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0087	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0088	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0089	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	400 LF		
0090	7456000000-E	1726	LEAD-IN CABLE	1,320 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0092	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0093	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	1 EA		
STRUCTURE ITEMS						
0094	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24 + 18.00-L-)	Lump Sum	L.S.	
0095	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (24 + 18.00-L-)	Lump Sum	L.S.	
0096	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	115.6 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24 + 18.00-L-)	Lump Sum	L.S.	
0098	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	16,882 LB		
0099	8384000000-E	450	HP14X73 STEEL PILES	1,455 LF		
0100	8385000000-E	450	PP ** X **** STEEL PILES (24" X 0.625")	2,565 LF		
0101	8475000000-E	460	TWO BAR METAL RAIL	339.33 LF		
0102	8517000000-E	460	1'-****X ***** CONCRETE PARAPET (1'-2" X 2'-8 1/2")	355.22 LF		
0103	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	185 TON		
0104	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	215 SY		
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,189.58	LF	
0107	8860000000-N	SP	GENERIC STRUCTURE ITEM EPOXY SAND SURFACE	Lump Sum	L.S.	
0108	8860000000-N	SP	GENERIC STRUCTURE ITEM RAILING SYSTEM	Lump Sum	L.S.	
0109	8874000000-E	SP	GENERIC STRUCTURE ITEM SCOUR PROTECTION STONE	20	TON	
0110	8897000000-N	SP	GENERIC STRUCTURE ITEM PDA ASSISTANCE	3	EA	
0111	8897000000-N	SP	GENERIC STRUCTURE ITEM PDA TESTING	3	EA	
0112	8897000000-N	SP	GENERIC STRUCTURE ITEM PILE REDRIVES	25	EA	
0113	8897000000-N	SP	GENERIC STRUCTURE ITEM PIPE PILE PLATES	27	EA	

1103/Mar14/Q74724.03/D545066000000/E113

Total Amount Of Bid For Entire Project :

C201561 (B-3445)
COUNTY: Currituck

2/16/99

Contract No: C201561
County: Currituck

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General