6/20/00

COMPUTED BY: _____ DATE: _____
CHECKED BY: _____ DATE: _____

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

MAP #5

PROJECT REFERENCE NO.	SHEET NO.
37613, ETC.	3-G

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

STATION	LOCATION (LT,RT, OR CL)	STRUCTURE NO. FROM	STRUCTURE NO. TO	TOP ELEVATION	INVERT ELEVATION	INVERT ELEVATION	SLOPE CRITICAL	CLASS III R.C. PIPE (UNLESS NOTED OTHERWISE) 12"	15"	18"	24"	30"	36"	42"	48"	BITUMINOUS COATED C.S. PIPE TYPE B (UNLESS NOTED OTHERWISE) 12" .064	15" .064	18" .064	24" .064	30" .079	36" .079	42" .109	48" .109	15" SIDE DRAIN PIPE	18" SIDE DRAIN PIPE	24" SIDE DRAIN PIPE	ENDWALLS STD. 838.01 OR STD. 838.11 (UNLESS NOTED OTHERWISE) CU. YDS. R.C.P.	CU. YDS. C.S.P.	QUANTITIES FOR ENDWALLS FOR STRUCTURES * TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (0.5 X COL. 'B') LIN. FT. A	LIN. FT. B	PER EACH (0' THRU 5.0')	5.0' THRU 10.0'	10.0' AND ABOVE	C.B. STD. 840.01 OR STD. 840.02	FRAME, GRATES AND HOOD STANDARD 840.03 TYPE OF GRATE E	F	G	D.I. STD. 840.14 OR STD. 840.15	D.I. FRAME & GRATE STD. 840.16	M.D.I. TYPE "A" STD. 840.17 OR 840.26	M.D.I. TYPE "B" STD. 840.18 OR 840.27	M.D.I. TYPE "D" STD. 840.19 OR 840.28	M.D.I. FRAME WITH GRATE STD. 840.22	M.D.I. FRAME WITH TWO GRATES STD. 840.22	M.D.I. (N.S.) FRAME WITH GRATE STD. 840.24	M.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.24	J.B. STD. 840.31 OR 840.32	PARALLEL PIPE END SECTION NUMBER AND SIZE STD. 310.02	CORR. STEEL ELBOWS NO. & SIZE	CONC. COLLARS CL. "B" C.Y. STD 840.72	CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71	PIPE REMOVAL LIN.FT.	REMARKS
11+60	RT	1			456.10	453.00																	52																									
13+60	RT	2			462.96	459.36																	76																									
15+70	RT	3			445.44	444.24						20																																		.65			
19+25	RT	4			478.51	477.7				20																																			.45			
19+85	LT	5		486.50	482.50	482.00				8																					1					1	1										.45			REMOVE DI
20+50	LT	6			488.00	482.50				104																																					1-18		.13	40	REMOVE 18" RCP AND DI
22+40	RT	7			484.69	484.38					8																																				.55			
22+95	LT	8			490.36	489.04					28																																				.55			REMOVE HEADWALL
25+25	RT	9			489.26	488.37				12																																					.45			
25+47	LT	10		497.00	495.25	494.38				16																					1					1	1										.45			REMOVE DI
29+75	RT	11			479.74	479.58					8																																				.55			
TOTALS										160	44	20											128								2					2	2									1-18		SAY=4	SAY=1	40	

ABBREVIATIONS

C.B.	CATCH BASIN
N.D.I.	NARROW DROP INLET
D.I.	DROP INLET
M.D.I.	MEDIAN DROP INLET
M.D.I. (N.S.)	MEDIAN DROP INLET (NARROW SLOT)
J.B.	JUNCTION BOX
M.H.	MANHOLE
T.B.D.I.	TRAFFIC BEARING DROP INLET
T.B.J.B.	TRAFFIC BEARING JUCTION BOX

$$$$SYSTIME$$$$
$$$$DGN$$$$
$$$$USERNAME$$$$