

PROJECT NO.	SHEET NO.
37613, 37814	1-G

## THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TEMPORARY WORK ZONE TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 120 M WHITE THERMO	4" X 120 M YELLOW THERMO	8" X 120 M YELLOW THERMO	24" X 120 M WHITE THERMO	THERMO STR ARROW 90 M	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	4" WHITE PAINT	4" YELLOW PAINT	PAINT LT ARROW	SNOW PLOWABLE MARKERS
					LS	LF	LF	LF	LF	LF	EA	EA	EA	LF	LF	EA	EA
37613	Randolph	2	US 64	FROM DAVIDSON/RANDOLPH COUNTY LINE TO 0.2 MILE WEST OF SR 1401 (KENNEDY FARM ROAD)	0.08	8,470	212	9,885	65		4	1					98
37613	Randolph	3	US 64	FROM 0.2 MILE WEST OF SR 1401 (KENNEDY FARM ROAD) TO 0.1 MILE WEST OF SR 1344 (OLD US 64)	0.13	17,580	424	19,580	210	110	8	2					185
37613	Randolph	4	US 64	FROM 0.1 MILE WEST OF SR 1344 (OLD US 64) TO 475 FEET WEST OF SR 1807 (KINDLEY ROAD)	0.14	18,210	286	21,340	430	150	4	5	1				242
37613	Randolph	5	US 64	FROM 475 FEET WEST OF SR 1807 (KINDLEY ROAD) TO 330 FEET WEST OF SR 1382 (TABERNACLE SCHOOL ROAD)	0.06	8,470	162	10,220	140	30	4	11					150
37613	Randolph	6	US 64	FROM 330 FEET WEST OF SR 1382 (TABERNACLE SCHOOL ROAD) TO 0.13 MILE WEST OF SR 1416 (OLD LEXINGTON ROAD)	0.14	18,470	124	19,005	100	50	4	2	1				140
37613	Randolph	7	US 64	FROM 0.13 MILE WEST OF SR 1416 (OLD LEXINGTON ROAD) TO 280 FEET WEST OF SR 1418 (SPENCER MEADOW ROAD)	0.13	12,070	248	14,700	310	60	10	3	1	12,000	15,000	4	255
37613	Randolph	8	US 64	FROM 280 FEET WEST OF SR 1418 (SPENCER MEADOW ROAD) TO 310 FEET WEST OF SR 1419 (LOWE COUNTRY ROAD)	0.02	5,800	210	5,780		100	4	2		6,000	6,000	2	40
37613	Randolph	9	US 64	FROM 310 FEET WEST OF SR 1419 (LOWE COUNTRY ROAD) TO SR 1420 (BACK CREEK ROAD)	0.04	4,950	70	4,880		30	2		1	5,000	5,000	1	45
37613	Randolph	10	US 64	FROM 0.13 MILE WEST OF SR 1420 (BACK CREEK ROAD) TO 0.14 MILE WEST OF SR 1424 (WESTCHAPEL ROAD)	0.17	24,450	692	26,300	200	100	8	2	2	25,000	26,000	4	230
37613	Randolph	11	US 64	FROM 0.14 MILE WEST OF SR 1424 (WESTCHAPEL ROAD) TO 0.2 MILE EAST OF SR 1323 (OAKLEAF ROAD)	0.08	11,900	212	13,990	100	60	4	9		12,000	14,000	9	290
<b>TOTAL FOR PROJ NO. 37613</b>					<b>0.99</b>	<b>130,370</b>	<b>2,640</b>	<b>145,680</b>	<b>1,555</b>	<b>690</b>	<b>52</b>	<b>37</b>	<b>6</b>	<b>60,000</b>	<b>66,000</b>	<b>20</b>	<b>1,675</b>
						<b>148,320</b>						<b>95</b>		<b>126,000</b>			
37814	Davidson	1	US 64	FROM 0.13 MILE WEST OF SR 2098 (KINDLEY ROAD) TO DAVIDSON/RANDOLPH COUNTY LINE	0.01	1,760	212	2,405	70	100	4	1					42
<b>TOTAL FOR PROJ NO. 37814</b>					<b>0</b>	<b>1,760</b>	<b>212</b>	<b>2,405</b>	<b>70</b>	<b>100</b>	<b>4</b>	<b>1</b>					<b>42</b>
						<b>2,617</b>						<b>5</b>					
<b>GRAND TOTAL</b>					<b>1</b>	<b>132,130</b>	<b>2,852</b>	<b>148,085</b>	<b>1,625</b>	<b>790</b>	<b>56</b>	<b>38</b>	<b>6</b>	<b>60,000</b>	<b>66,000</b>	<b>20</b>	<b>1,717</b>
						<b>150,937</b>						<b>100</b>		<b>126,000</b>			