

PROJECT: 37613, ETC.
COUNTY: RANDOLPH & DAVIDSON

PROJECT SPECIAL PROVISIONS
UTILITY

UTILITY CONFLICTS:

GENERAL:

THE FOLLOWING UTILITY COMPANIES HAVE FACILITIES THAT WILL BE IN CONFLICT WITH THE CONSTRUCTION OF THIS PROJECT:

- A. ENERGY UNITED
- B. DAVIDSON WATER, INC.
- C. RANDOLPH ELECTRIC MEMBERSHIP CORP. (EMC)
- D. PROGRESS ENERGY
- E. SPRINT TELEPHONE
- F. NORTH STATE TELEPHONE
- G. TIME WARNER CABLE

THE CONFLICTING FACILITIES OF THESE CONCERNS WILL BE ADJUSTED PRIOR TO THE DATE OF AVAILABILITY, UNLESS OTHERWISE NOTED AND THEREFORE LISTED IN THESE SPECIAL PROVISIONS FOR THE BENEFIT OF THE CONTRACTOR. ALL UTILITY WORK LISTED HEREIN WILL BE DONE BY THE UTILITY OWNERS. ALL UTILITIES ARE SHOWN ON THE PLANS FROM THE BEST AVAILABLE INFORMATION.

THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 105.8 OF THE STANDARD SPECIFICATIONS.

UTILITIES REQUIRING ADJUSTMENT:

- A. ENERGY UNITED

THE UTILITY POLE AT STATION 14+00± LT -L- ON MAP #1 (INTERSECTION WITH SR 2098, KINDLEY ROAD) WILL REMAIN IN PLACE AS CONTRACTOR COMPLETES ROUGH GRADING. PRIOR TO COMPLETION OF ROUGH GRADING, THE CONTRACTOR SHALL CONTACT THE RESIDENT ENGINEER WHO WILL GIVE ENERGY UNITED FIVE (5) WORKING DAY'S NOTICE. ENERGY UNITED SHALL HAVE TEN (10) CALENDAR DAYS TO COMPLETE THE WORK. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND UTILITIES.

THE UTILITY POLES AT STATION 26+60± LT -L- AND STATION 29+60± LT -L- ON MAP #2 (INTERSECTION WITH SR 2098, KINDLEY ROAD) WILL REMAIN IN PLACE. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND UTILITIES.

THE UTILITY POLES AT STATION 22+40± RT -L- AND STATION 22+26± LT -L- ON MAP #3 (INTERSECTION WITH SR 1401, KENNEDY FARM ROAD) WILL REMAIN IN PLACE AS CONTRACTOR COMPLETES ROUGH GRADING. PRIOR TO COMPLETION OF ROUGH GRADING, THE CONTRACTOR SHALL CONTACT THE RESIDENT ENGINEER WHO WILL GIVE ENERGY UNITED FIVE (5) WORKING DAY'S NOTICE. ENERGY UNITED SHALL HAVE TEN (10) CALENDAR DAYS TO COMPLETE THE WORK. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND UTILITIES.

B. DAVIDSON WATER, INC.

THE WATERLINE FROM STATION 13+15± RT -L- ON MAP #1 TO STATION 32+25± RT -L- ON MAP #2 (INTERSECTION WITH SR 2098, KINDLEY ROAD) SHALL REMAIN IN PLACE UNTIL CONTRACTOR HAS PLACED THE NECESSARY FILL FOR THE INSTALLATION OF THE NEW WATERLINE WITHIN THIS LOCATION. PRIOR TO THE COMPLETION OF PLACING THE NECESSARY FILL, THE CONTRACTOR SHALL CONTACT THE RESIDENT ENGINEER WHO WILL GIVE DAVIDSON WATER, INC. FIVE (5) WORKING DAY'S NOTICE. DAVIDSON WATER, INC. SHALL HAVE TWENTY-FOUR (24) CALENDAR DAYS TO COMPLETE THE WORK. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND UTILITIES.

THE WATERLINE FROM STATION 10+75± RT -L- TO STATION 29+25± RT -L- ON MAP #3 (INTERSECTION WITH SR 1401, KENNEDY FARM ROAD) SHALL REMAIN IN PLACE UNTIL CONTRACTOR HAS PLACED THE NECESSARY FILL FOR THE INSTALLATION OF THE NEW WATERLINE WITHIN THIS LOCATION. PRIOR TO THE COMPLETION OF PLACING THE NECESSARY FILL, THE CONTRACTOR SHALL CONTACT THE RESIDENT ENGINEER WHO WILL GIVE DAVIDSON WATER, INC. FIVE (5) WORKING DAY'S NOTICE. DAVIDSON WATER, INC. SHALL HAVE TWENTY-FOUR (24) CALENDAR DAYS TO COMPLETE THE WORK. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND UTILITIES.

NOTE: THE CONTRACTOR SHALL NOT GIVE NOTICE TO PROCEED WITH WORK AT SECOND LOCATION UNTIL DAVIDSON WATER, INC. HAS COMPLETED WORK IN FIRST LOCATION.

C. RANDOLPH EMC

THE UTILITY POLES AT STATION 43+80±, 46+20± AND 53+30± LT -L- ON MAP #11 WILL BE SET AT EXTRA DEPTH IN SAME LOCATION PRIOR TO THE DATE OF AVAILABILITY. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND NEW UTILITY POLES.

D. PROGRESS ENERGY

THE UTILITY POLE AT STATION 48+50± LT -L- ON MAP #11 WILL BE SET AT EXTRA DEPTH IN SAME LOCATION PRIOR TO THE DATE OF AVAILABILITY. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND NEW UTILITY POLE.

THE UTILITY POLES FROM STATION 60+00± LT -L- TO STATION 65+00± LT -L- ON MAP #11 WILL REMAIN IN PLACE. CONTRACTOR SHALL TAKE CAUTION WHILE WORKING AROUND UTILITIES.

E. SPRINT TELEPHONE

RELOCATION OF UTILITIES ON MAP #11 WILL BE COMPLETED BY JULY 15, 2006.