

County : Randolph, Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	183 TON		
0004	0343000000-E	310	15" SIDE DRAIN PIPE	1,002 LF		
0005	0344000000-E	310	18" SIDE DRAIN PIPE	60 LF		
0006	0345000000-E	310	24" SIDE DRAIN PIPE	64 LF		
0007	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	370 LF		
0008	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,000 LF		
0009	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	270 LF		
0010	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	32 LF		
0011	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	24 LF		
0012	0453000000-E	310	*** PIPE END SECTION (15")	20 EA		
0013	0453000000-E	310	*** PIPE END SECTION (18")	7 EA		
0014	0453000000-E	310	*** PIPE END SECTION (24")	1 EA		
0015	0995000000-E	340	PIPE REMOVAL	1,120 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0017	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.72 SMI		
0018	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	90,371 SY		

County : Randolph, Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	2,222 SY		
0020	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	8,881 TON		
0021	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	4,817 TON		
0022	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	45,764 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	610 TON		
0024	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,746 TON		
0025	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,201 TON		
0026	2253000000-E	840	PIPE COLLARS	20 CY		
0027	2264000000-E	840	PIPE PLUGS	5 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	13 EA		
0029	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9 EA		
0030	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0031	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0032	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0033	3030000000-E	862	STEEL BM GUARDRAIL	10,512 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	406.25 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	35 EA		
0036	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	5 EA		

County : Randolph, Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	10 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	47 EA		
0039	3628000000-E	876	PLAIN RIP RAP, CLASS I	390 TON		
0040	3649000000-E	876	PLAIN RIP RAP, CLASS B	662 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,498 SY		
0042	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY WORK ZONE TRAFFIC CONTROL	Lump Sum	L.S.	
0043	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	132,130 LF		
0044	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	150,937 LF		
0045	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,625 LF		
0046	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	790 LF		
0047	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	100 EA		
0048	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	126,000 LF		
0049	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20 EA		
0050	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,717 EA		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	5,040 LF		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,220 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	615 TON		
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	230 LF		

County : Randolph, Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6030000000-E	1630	SILT EXCAVATION	2,100 CY		
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	800 LF		
0057	6084000000-E	1660	SEEDING & MULCHING	29 ACR		
0058	8203000000-E	420	CLASS A CONCRETE (RETAINING WALL)	6.8 CY		
0059	8252000000-E	425	REINFORCING STEEL (RETAINING WALL)	742 LB		
1030/Mar16/Q602499.77/D168042100000/E59			Total Amount Of Bid For Entire Project :			

C201579  
COUNTIES: Randolph & Davidson

2/16/99

Contract No: C201579  
Counties: Randolph & Davidson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General