



HYDE COUNTY

PROJECT: 33006.1.1 (B-3348)

INDEX OF SHEETS

SHEET NUMBER

- 1
- 1-A
- 1-B
- 2
- 2-A THRU 2-B
- 2-C THRU 2-F
- 2-G
- 2-H THRU 2-J
- 2-K
- 2-L THRU 2-O
- 3-A
- 3-B
- 4 THRU 5
- 6 THRU 7
- TCP-1 THRU TCP-12
- EC-1 THRU EC-7
- SIG-1 THRU SIG-7
- U-1 THRU U-5
- U0-1 THRU U0-3
- X-1A
- X-1B
- X-2 THRU X-26
- S-1 THRU S-76

SHEET

- TITLE SHEET
- INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARDS
- CONVENTIONAL SYMBOLS
- PAVEMENT SCHEDULE, DETAIL OF WEDGING, AND DETAIL OF UNDERCUT EXCAVATION
- TYPICAL SECTIONS
- GUARDRAIL INSTALLATION
- DETAIL OF TYPE III-SHOP CURVED
- DETAIL FOR STRUCTURE ANCHOR UNITS
- DETAIL FOR TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC
- REINFORCED BRIDGE APPROACH FILL DETAIL
- LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER), SUMMARY OF GUARDRAIL, SUMMARY OF EARTHWORK, AND SUMMARY OF PAVEMENT REMOVAL
- PARCEL INDEX SHEET
- PLAN SHEETS
- PROFILE SHEETS
- TRAFFIC CONTROL PLANS
- EROSION CONTROL PLANS
- SIGNAL PLANS
- UTILITY CONSTRUCTION UTILITIES BY OTHERS PLANS
- INDEX OF CROSS SECTIONS
- CROSS SECTION SUMMARY SHEET
- CROSS SECTIONS
- STRUCTURE PLANS

GENERAL NOTES: 2002 SPECIFICATIONS EFFECTIVE: 01-15-02

GRADE LINE: GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING: CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION: ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION: ASPHALT AND EARTH SHOULDER CONSTRUCTION ON HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

SIDE ROADS: THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

GUARDRAIL: THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING: SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING" OR "TEMPORARY SHORING-BARRIER SUPPORTED" DEPENDING UPON THE LOCATION OF THE SHORING.

END BENTS: THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES: UTILITY OWNERS ON THIS PROJECT ARE TIDELAND ELECTRIC, SPRINT, ENGLEHERD SANITATION DISTRICT.

RIGHT-OF-WAY MARKERS: ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.

EFF. 01-15-02

ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January 15, 2002 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE	DIVISION 2 - EARTHWORK
200.02	Method of Clearing - Method II	
225.02	Guide for Grading Subgrade - Secondary and Local	
225.04	Method of Obtaining Superelevation - Two Lane Pavement	
225.06	Method of Grading Sight Distance at Intersections	
		DIVISION 3 - PIPE CULVERTS
300.01	Method of Pipe Installation - Method 'A'	
		DIVISION 5 - SUBGRADE, BASES AND SHOULDERS
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I	
		DIVISION 8 - INCIDENTALS
862.01	Guardrail Placement	
862.03	Structure Anchor Units	