R:\Roadway\XSC\appended earthwork\appended_L_FULL_ear.log

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
B-4319	X-1A

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+30.00	0	0
12+50.00	0	8
13+00.00	2	42
13+50.00	2	26
14+00.00	2	17
14+50.00	2	21
15+00.00	1	29
15+50.00	7	46
15+84.00	10	41

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+74.00	1	11
17+00.00	6	49
17+50.00	6	86
18+00.00	1	55
18+50.00	1	31
19+00.00	1	46
19+50.00	1	62
20+00.00	2	50
20+30.00	0	11