

UTILITY CONFLICTS

It shall be the responsibility of the Contractor to contact all affected utility owners and determine the precise locations of all utilities prior to beginning construction. Utility owners shall be contacted a minimum of 48 hours prior to the commencement of operations. Special care shall be used in working around or near existing utilities, protecting them when necessary to provide uninterrupted service. In the event that any utility service is interrupted, the Contractor shall notify the utility owner immediately and shall cooperate with the owner, or his representative, in the restoration of service in the shortest time possible. Existing fire hydrants shall be kept accessible to fire departments at all times.

The Contractor shall adhere to all applicable regulations and follow accepted safety procedures when working in the vicinity of utilities in order to insure the safety of construction personnel and the public.

Utility relocation will not be complete prior to the start of construction, therefore, the contractor will have to coordinate with the utility companies during the relocation.

SEEDING AND MULCHING:

(East)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

All Roadway Areas:

March 1 - August 31

50# (55kg) Tall Fescue
 10# (12kg) Centipede
 25# (28kg) Bermudagrass (hulled)
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

September 1 - February 28

50# (55kg) Tall Fescue
 10# (12kg) Centipede
 35# (40kg) Bermudagrass (unhulled)
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

Waste and Borrow Locations:

January 1 - December 31

75# (85kg) Tall Fescue
 25# (28kg) Bermudagrass (hulled)
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

75# (85kg) Tall Fescue
 35# (40kg) Bermudagrass (unhulled)
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

Note: 50# (55 kg) of Bahiagrass may be substituted for either Centipede or Bermudagrass only upon Engineer's request.

Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk
Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

On cut and fill slopes 2:1 or steeper Centipede shall be applied at the rate of 5 pounds per acre (6 kilograms per hectare) and add 20# (23kg) of Sericea Lespedeza from January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.