

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,550 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	250 CY		
0007	0106000000-E	230	BORROW EXCAVATION	650 CY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	47 TON		
0009	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	68 LF		
0010	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	76 LF		
0011	0995000000-E	340	PIPE REMOVAL	276 LF		
0012	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0013	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	14,500 LB		
0014	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0015	1245000000-E	SP	SHOULDER RECONSTRUCTION	11.72 SMI		
0016	1330000000-E	607	INCIDENTAL MILLING	3,800 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,800 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	850 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	11,265 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,008 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0022	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,000 TON		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0024	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0025	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0026	2612000000-E	848	6" CONCRETE DRIVEWAY	309 SY		
0027	2830000000-N	858	ADJUSTMENT OF MANHOLES	3 EA		
0028	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5 EA		
0029	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	72,680 LF		
0030	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	59,796 LF		
0031	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	550 LF		
0032	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	200 LF		
0033	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0034	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	37 EA		
0035	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	770 EA		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	400 LF		
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		
0039	6042000000-E	1632	1/4" HARDWARE CLOTH	30 LF		
0040	6084000000-E	1660	SEEDING & MULCHING	18.48 ACR		
0041	6090000000-E	1661	SEED FOR REPAIR SEEDING	25 LB		
0042	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.13 TON		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0043	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	296 LF		
------	--------------	-----	---------------------------------	-----------	--	--

AA1

*** OR ***

0044	0986000000-E	SP	GENERIC PIPE ITEM 15" HDPE PIPE CULVERTS	296 LF		
------	--------------	----	---	-----------	--	--

AA2

*** OR ***

0045	0986000000-E	SP	GENERIC PIPE ITEM 15" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, 0.064" THICK	296 LF		
------	--------------	----	--	-----------	--	--

AA3

***** END SCHEDULE AA *****

0808/May19/Q178216.45/D110670500000/E45

Total Amount Of Bid For Entire Project :

C201431
COUNTY: Harnett

2/16/99

Contract No: C201431
County: Harnett

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General