

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+ 17.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	625 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	45 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	8 TON		
0009	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	72 LF		
001C	1121000000-E	520	AGGREGATE BASE COURSE	160 TON		
0011	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	555 TON		
0013	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	445 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		
0015	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0016	2619000000-E	850	4" CONCRETE PAVED DITCH	25 SY		
0017	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
001E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1	EA	
002C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1	EA	
0021	3649000000-E	876	PLAIN RIP RAP, CLASS B	15	TON	
0022	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	285	SY	
0023	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	4.5	SF	
0024	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	37.75	SF	
002E	4082000000-E	903	SUPPORTS, WOOD	84	LF	
002E	4096000000-N	904	SIGN ERECTION, TYPE D	1	EA	
0027	4102000000-N	904	SIGN ERECTION, TYPE E	6	EA	
002E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	1	EA	
002E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	6	EA	
003C	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	4	EA	
0031	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	192	SF	
0032	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	144	SF	
0033	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	40	SF	
0034	4430000000-N	1130	DRUMS	25	EA	
003E	4435000000-N	1135	CONES	30	EA	
003E	4446100000-E	SP	BARRICADES (TYPE III)	60	LF	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4450000000-N	1150	FLAGGER	720	HR	
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,200	LF	
003E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	40	LF	
004C	6000000000-E	1605	TEMPORARY SILT FENCE	1,450	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	55	TON	
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	55	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0047	6029000000-E	SP	SAFETY FENCE	570	LF	
004E	6030000000-E	1630	SILT EXCAVATION	150	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	150	SY	
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	200	LF	
0051	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	100	SY	
0052	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
0053	6087000000-E	1660	MOWING	0.5	ACR	
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0058	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0059	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		

STRUCTURE ITEMS

0060	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12 + 17.50 -L-)	Lump Sum	L.S.	
0061	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	45.8 CY		
0062	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12 + 17.50 -L-)	Lump Sum	L.S.	
0063	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	6,154 LB		
0064	8329000000-E	450	12" PRESTRESSED CONC PILES	900 LF		
0065	8433000000-E	452	*** STEEL SHEET PILES (18")	2,772 SF		
0066	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-7" X 11 1/2")	105.48 LF		
0067	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0068	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	738.35 LF		
0069	8867000000-E	SP	GENERIC STRUCTURE ITEM SPECIAL STEEL 2-BAR METAL RAIL	90.22 LF		

C201241
COUNTY: Hyde

2/16/99

Contract No: C201241
County: Hyde

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General